


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Edwards County. Sec. 1 Twp. 24 Rge. 16 ~~W~~ (W)
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines NE NE NE
Lease Owner Heathman & Company, Inc.
Lease Name Stock Well No. 1
Office Address 254 No. Washington, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed July 17, 19 52
Application for plugging filed Aug. 1, 19 52
Application for plugging approved July 17, 19 52
Plugging commenced July 17, 19 52
Plugging completed July 17, 19 52
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives, Box 118, Pratt, Kansas
Producing formation Depth to top Bottom Total Depth of Well 4257' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
See Driller's Log						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole to 300' with heavy mud. Set Plug and cemented with 20 sacks cement through drill pipe. Filled hole to 30', set plug, cemented with 10 sacks cement.

REC'D
STATE CORP. COM.
Rec'd 8-5-52

CONSULTING

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor The Carl Todd Drilling Company
Address 404 KEH Building, Wichita, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK
I, Carl Todd, Contractor (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God,

(Signature) Carl Todd leg. J. Sealey
404 KEH Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 1st day of August, 1952

Ada C. May
Notary Public.

My commission expires August 31, 1955 23-8390-s 6-51-20M

PLUGGING
FILE SEC. 1-26 R(11)
BOOK PAGE 31

THE CARL TODD DRILLING COMPANY
404 KFH Building,
Wichita 2, Kansas

Heathman & Company, Inc., et al.
STOCK No. 1
NE/4 NE/4 NE/4 1-24S-16W
Edwards County, Kansas

Date Commenced: July 3, 1952
Date Completed: July 17, 1952

Rotary Tools: 0' to 4257'

Elevation: 2052' DF

Casing Record:
8-5/8" casing cemented at 319'
with 220 sacks cement.

LOG

0	40	Sand, clay
40	110	Sand
110	320	Shale, shells
320	850	Red shale, sand
850	995	Red bed, shells
995	1030	Anhydrite
1030	1390	Shale, shells
1390	1800	Shale, shells
1800	1835	Shale
1835	2180	Lime, shale
2180	2295	Lime
2295	2410	Broken lime
2410	2830	Lime, shale
2830	2935	Lime
2935	3145	Shale, lime
3145	3230	Lime
3230	3395	Lime, shale
3395	3475	Lime
3475	3550	Lime (chalky)
3550	3630	Lime
3630	3705	Lime, shale
3705	3805	Lime
3805	4027	Lime
4027	4046	Lime, shale
4046	4085	Lime
4085	4172	Chert
4172	4234	Simpson
4235	4257	Lime - Total Depth

Formation Tops

Heebner	3550
Toronto	3572
Base-Oread	3593
Brown Lime	3687
Lansing	3700
Viola	4072
Simpson	4172
Arbuckle	4239
R.T.D.	4257

Drill stem test - 4185' - 4210'
Tool open 45 minutes, weak blow
thruout, recovered 40' slight
oil cut mud and 60' salt water.
BHP 1200# in 15 minutes.

I, Carl Todd, do hereby certify
that the above log is correct to
the best of my knowledge and
belief.

Carl Todd
by *Kay Griesinger*

RECEIVED
STATE CORPORATION COMMISSION
AUG - 5 1952
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC. LT 2410
BOOK PAGE 35 LINES 16
31