

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-047-20114-000

LEASE NAME Reaves

WELL NUMBER #2

SPOT LOCATION N/2 SW NW

SEC. 1 TWP. 24S RGE. 16W (E) or (W)

COUNTY Edwards

Date Well Completed \_\_\_\_\_

Plugging Commenced 6-10-86

Plugging Completed 6-30-86

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Messman Rinehart Corporation  
ADDRESS 500 Bitting Bldg. Wichita, Kansas 67202

PHONE # (316) 263-4211 OPERATORS LICENSE NO. \_\_\_\_\_

Character of Well Oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Kansas

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 4062'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	324'	none
				4-1/2"	4055'	2326'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

Plugged off bottom with sand to 4000' and 4 sacks cement. Shot pipe @3234', 3032', 2830', 2628', 2429', 2326', pulled a total of 74 joints of 4-1/2" casing. Plugged surface with 2 sks. hulls and 150 sks. econolite. Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050  
Address P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso, President (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347 Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 30 day of June, 19 86



Irene Hoover  
Notary Public

My Commission expires: \_\_\_\_\_

DRILLERS LOG

No. 2 Reaves

CASING RECORD:

8 5/8" @ 324'  
w/210 sx cement

4 1/2" @ 4065'  
w/135 sx cement

TOTAL DEPTH: 4062'

COMPANY: Messman-Rinehart Oil Co.

CONTRACTOR: Red Tiger Drilling Co.

COMMENCED: December 23, 1971

COMPLETED: January 4, 1972

DESCRIPTION:

N/2 SW NW  
1-24S-16W  
Edwards County,  
Kansas

ELEVATION:


<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Soil	0	15	
Sand, Shale Stringers	15	107	
Shale & Clay	107	325	
Red Bed	325	409	
Sand & Red Bed	409	528	
Red Bed	528	964	
Anhydrite	964	986	
Shale	986	1289	
Shale & Lime	1289	1485	
Shale & Shells	1485	1900	
Lime & Shale	1900	3320	
Lime	3320	3430	
Lime & Shale	3430	3603	
Lime	3603	3915	
Lime & Shale	3915	3970	
Conglomerate	3970	4057	
Arbuckle	4057	4062	

I certify that this a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

*Jim Farrice*  
Jim Farrice

Subscribed and sworn to before me this 6th day of January, 1972.



*Virginia K. Albert*  
Notary Public

My Commission Expires:  
July 23, 1974

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 12 1986  
CONSERVATION DIVISION  
Wichita, Kansas