

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-185-10986-0001

LEASE NAME Rixon

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER "A" #2

990 Ft. from S Section Line

2970 Ft. from E Section Line

LEASE OPERATOR Rockhold Engineering, Inc.

SEC. 7 TWP. 24 RGE. 13 (E) or (W)

ADDRESS Box 698, Great Bend, Kansas 67530

COUNTY Stafford

PHONE# (316) 792-2506 OPERATORS LICENSE NO. 5111

Date Well Completed 10-56

Character of Well Gas

Plugging Commenced 6-15-88

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 1-10-89

The plugging proposal was approved on January 6, 1989 (date)

by Dan Goodrow (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached? With application

Producing Formation Depth to Top Bottom T.D. 3981'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put In | Pulled out |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8-5/8" | 221' | None |
| | | | | 5-1/2" | 3978' | 2,323.32' |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Dumped sand to 3600' & 5 sacks cement. Shot casing at 3000', 2400', 2200', 2000', 1800'. Pulled 73 joints of 5-1/2" casing. B.J. Titan plugged well with 400# hulls 10 sacks gel, 50 sacks cement, 10 sacks gel, 100# hulls, released plug and pumped 120 sacks 60/40 pozmix cement with 6% gel. Max. press. 450 psi & shut in 300 psi.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Rockhold Engineering, Inc.

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold

(Address) James W. Rockhold
Box 698, Great Bend, Kansas 67530

SUBSCRIBED AND SWORN TO before me this 11th day of January, 1989



Iona M. Leatherman
Notary Public

My Commission Expires: