

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

NORTH

Locate well correctly on above
Section Plat

Pratt County, Sec. 28 Twp. 29 Rge. 14 (E) W. (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines 990' E. & 990' N. of S $\frac{1}{4}$ Cor.

Lease Owner Cities Service Oil Company

Lease Name Frost Well No. 1

Office Address Bartlesville, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed February 24, 1953

Application for plugging filed February 24, 1953

Application for plugging approved February 24, 1953

Plugging commenced February 24, 1953

Plugging completed February 24, 1953

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production None 19__

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives

Producing formation Artuckle Depth to top 4700 Bottom 4700 Total Depth of Well 4700 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	400'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

4700-300', mud
300-235', wood plug and hulls, and 20 sacks cement.
235- 35', mud
35' to base of cellar, wood plug and 10 sacks cement.

RCVP
03-03-53

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Barbour Drilling Company

Address Tulsa, Oklahoma

STATE OF Kansas, COUNTY OF Barton, ss.

V. M. Conover (employee of owner) or owner or operator of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) V. M. Conover

Box 751, Great Bend, Kansas


(Address)

SUBSCRIBED AND SWORN to before me this 25th day of February, 19 53

W. B. Smith

Notary Public.

My commission expires March 12, 1955.



WELL RECORD

Company Cities Service Oil Co. Well No. 1 Farm Frost
 Location 990' North and 990' East of E/4 Cor. Sec. 28 T. 29 R. 14W
 Elevation 1983 (1977 Gr.) County Pratt State Kansas
 Drlg. Comm. February 3, 1953 Contractor Barbour Drilling Company
 Drlg. Comp. February 23, 1953 Acid None
 T. D. 4700' Initial Prod. None - Dry Hole; P. & A. 2-24-53.

CASING REQUIRED:

8-5/8" O 4 1/4' con. 250 ex cement

FORMATION RECORD:

surface clay & shale	0-85
sand	195
red bed & shells	800
shale & shells	1785
lime & shale	2465
lime	2560
lime & shale	2745
shale & lime	2990
shale	3250
shale & lime	3320
lime & shale	3505
lime	3955
lime & shale	4005
lime	4660
shale	4667
lime	4700 T. D.

Brown Limestone	4006'
Lansing	4030'
Viola	4523'
Simpson Shale	4555'
Simpson Sand	4562'
Arbuckle	4667'
Penetration	33'
Total Depth	4700'

Drill Stem Test 4523-55, open 1 hr., recovered 160' gassy mud, 90' salt water with trace oil, and 810' salt water; B. H. P. 1315#/15 mins.

Drill Stem Test 4563-68, open 1 hr., recovered 20' mud; D. H. P. 138#/15 mins.

Drill Stem Test 4565-74, open 1 hr., recovered 945' salt water; B. H. P. 1190#/15 mins.

Drill Stem Test 4606-26, open 1 hr., recovered 540' slightly gassy and oily mud and 1540' salt water; B. H. P. 1230#/15 mins.

TOTOO STRAIGHT HOLE TEST:

900'	1/2°
1000'	1/2°
1500'	1°
2000'	1°
2500'	1°
3000'	3/4°
3500'	1°
4000'	1/2°

PLUGGING
 FILE REC 28 T 29 R 14W
 BOOK PAGE 8 LINE 8

STATE COMMISSION
 CONSERVATION DIVISION
 WASHINGTON, D. C.