

15-151-10057-00-01

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER \_\_\_\_\_

LEASE NAME A & W FARMS

WELL NUMBER #1

SPOT LOCATION NE/4 SW/4 SE/4

SEC 28 TWP 29S RGE 14W (E) or

COUNTY PRATT

Date Well Completed \_\_\_\_\_

Plugging Commenced 4-17-84

Plugging Completed 6-7-84

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR RAYMOND OIL COMPANY, INC.

ADDRESS ONE MAIN PLACE SUITE 900 WICHITA, KS. 67202

PHONE # (316) 267-4214 OPERATORS LICENSE NO. 5046

Character of Well OTT  
(Oil, Gas, D&A, SMD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? YES

Which KCC/KDHE Joint Office did you notify? DODGE CITY, KANSAS

Is ACD-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 4707'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASINO RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	418'	none
				4-1/2"	4534'	3599'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

Plugged off bottom with sand to 4150' and 4 sacks cement. Shot casing @ 3570', 3599' and pulled a total of 107 joints (3599') of 4-1/2" casing. Plugged surface with 3 hulls, 15 gel, 50 cement, 10 gel, 1 hull, released plug and displaced with 125 cement, 50/50 pos, 2% gel, 3% cc. Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050  
Address P.O. Box 347 Chase, Kansas 67524

6-13-1984

STATE OF Kansas COUNTY OF Rice, ss.

RECEIVED  
STATE CORPORATION COMMISSION

R. Darrell Kelso (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help us God.

JUN 13 1984

CONSERVATION DIVISION  
Wichita, Kansas

(Signature) R. Darrell Kelso

(Address) Box 347 Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 12 day of June, 1984

Jean Hoover  
NOTARY PUBLIC

My Commission expires \_\_\_\_\_

