


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Pratt County, Sec. 27 Twp. 29 Rge. 14 (X) (W)

Location as "NE/CNW/SW" or footage from lines SE SE NW
Lease Owner Musgrove Petroleum Corporation
Lease Name Kerr Well No. 1
Office Address 518 Petroleum Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed March 5, 19 53
Application for plugging filed March 10, 19
Application for plugging approved 19
Plugging commenced March 5, 19 53
Plugging completed March 5, 19 53
Reason for abandonment of well or producing formation Dry



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. M.A. Rives, Pratt, Kansas
Producing formation Depth to top Bottom Total Depth of Well 4557 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	390'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set first plug at 300' with 20 sacks of cement.
Second plug at 35' with 10 sacks of cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Musgrove Petroleum Corporation
Address 518 Petroleum Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Gordon L. Koelling (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gordon L. Koelling
518 Petroleum Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of March, 19 53

Mary L. Susan
Notary Public.

My commission expires November 14, 1956

PLUGGING
FILE SEC 27 T 29 R 14 W
BOOK PAGE 82 LINE 89

24-2675-8

2-52-20M



RECEIVED
STATE CORPORATION COMMISSION

MAR 11 1953

3-11-1953

CONSERVATION DIVISION
Wichita, Kansas

CONTRACTOR'S WELL LOG

COMPANY:	Musgrove Petroleum Corporation
CONTRACTOR:	Musgrove Petroleum Corporation
FARM:	Kerr #1
LOCATION:	SE SE NW Section 27-29-14 Pratt County, Kansas
COMMENCED:	February 11, 1953
COMPLETED:	March 5, 1953

0	30	Sand and shells
30	140	Sand and gravel
140	450	Shale and red bed
450	763	Red bed
763	798	Anhydrite
798	1800	Shale and shells
1800	1860	Salt
1860	2085	Shale and shells
2085	3460	Lime and shale
3460	3645	Lime
3645	3935	Lime and shale
3935	3968	Lime
3968	4130	Lime and shale
4130	4471	Lime
4471	4520	Lime and shale
4520	4532	Lime chert
4532	4545	Chert
4545	4557	shale
	4557	Rotary Total Depth

Set 390' of 8 5/8" with 250 sacks of cement.

Dry and abandoned.

STATE OF KANSAS)
COUNTY OF SEDGWICK) SS

PLUGGING
FILE SEC 27 T 29 R 14W
BOOK PAGE 82 LINE 39

I, GORDON L. KOELLING, do hereby verify that the above and foregoing is a true and correct copy of the log of the Kerr # 1 Section 27-29-14, Pratt County, Kansas, as reflected by the files of the Musgrove Petroleum Corporation.

MUSGROVE PETROLEUM CORPORATION

By Gordon L. Koelling
Secretary-Treasurer

Subscribed and sworn to before me a Notary Public in and for Sedgwick County, Kansas, this 10th day of March, 1953.

Mary L. Sumner
Notary Public

My Commission Expires: November 14, 1956.

RECEIVED
STATE CORPORATION COMMISSION

MAR 11 1953

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 27 T 29 R 14W
BOOK PAGE 82 LINE 39