

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Pratt SEC. 27 TWP. 29S RGE. 14 W
Location as in quarters or footage from lines:
NE NE NW

Lease Owner Raymond Oil Co., Inc.
 Lease Name Kerr Well No. #1
 Office Address One Main Place - Suite 900 Wichita, Ks. 67202
 Character of Well (Completed as Oil, Gas or Dry Hole): Dry
 Date Well Completed 1-23-84
 Application for plugging filed 1-23-84
 Plugging commenced 1-23-84
 Plugging completed 1-23-84
 Reason for abandonment of well or producing formation _____

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Warren Kirkpatrick
Producing formation _____ Depth to top _____ bottom T.D. 4679'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	343'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____
feet to _____ feet for each plug set.

- Spotted 50 sx. cement @ 4600' thru drill pipe.
- Spotted 50 sx. cement @ 790' thru drill pipe.
- Spotted 50 sx. cement @ 390' thru drill pipe.
- Spotted 10 sx. cement @ 40' thru drill pipe.
- Spotted 15 sx. cement in rathole.
- Spotted 5 sx. cement in water well.

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor White & Ellis Drilling, Inc.
401 E. Douglas, Suite 500, Wichita, Ks. 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.

Ernest Sifford (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) [Signature]
401 E. Douglas #500 Wichita
(Address) Kansas 67202

SUBSCRIBED AND SWORN TO before me this 8th day of January, 19 84




David F. Jamis
Notary Public.

My Commission expires:

RECEIVED
STATE CORPORATION COMMISSION

FEB 09 1984

CONSERVATION DIVISION
Wichita, Kansas



WHITE

ANDELLIS DRILLING, Inc.

DRILLERS LOG

OPERATOR: Raymond Oil Co., Inc. Suite 900 One Main Place Wichita, Kansas 67202

CONTRACTOR: White & Ellis Drilling, Inc., 401 E. Douglas, Suite 500, Wichita, Ks. 67202

Lease Name Kerr Well No. 1

Sec. 27 T. 29S R. 14W Spot NE NE NW

County Pratt State Kansas Elevation _____

Casing Record:

Surface: 8 5/8" @ 343' with 200 sx. 3%cc
2%gel

Production: _____ @ _____ with _____ sx.

Type Well: D & A Total Depth 4679'

Drilling Commenced 1-8-84 Drilling Completed 1-23-84

Formation	From	To	Tops	
Cellar	0	7	Lansing	4054
Sand	7	205	Arbuckle	4625
Clay, Sand	205	277		
Shale	277	1020		
Clay, Shale	1020	1424		
Shale, Lime	1424	2140		
Shale	2140	2555		
Sahle, Lime	2555	2714		
Lime, Shale	2714	2905		
Shale, Lime	2905	3230		
Lime, Shale	3230	3710		
Shale, Lime	3710	3835		
Lime, Shale	3835	3972		
Sand	3972	3990		
Lime, Shale	3990	4054		
Lime	4054	4560		
Conglomerate	4560	4625		
Lime	4625	4679		

RECEIVED
STATE CORPORATION COMMISSION

FEB 09 1984

CONSERVATION DIVISION
Wichita, Kansas