

15-155-00269-0000

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas


THE TEXAS CO.
E. Wipf No. 1.

SEC. 36 T. 22 R. 9 W
CWL SW SW
660' f SL 330' f WL W $\frac{1}{2}$ SW $\frac{1}{4}$

Total Depth. 3984' PB 3660'
Comm. 7-11-42 Comp. 8-12-42
Shot or Treated.
Contractor. Kiowa Drlg. Co.
Issued. 9-19-42

Rotary O-3984

County. Reno



CASING:

10 3/4"

5 1/2"

178' Cem.

3600' Cem.

Elevation.

Production. Dry

Figures Indicate Bottom of Formations.

clay	18	Tops:
sand	110	Anhydrite 315
red bed	315	Ft. Riley 1455
lime	350	(Base) Florence 1685
shale & shells	830	Topeka 2675
salt & shale	1130	Oil stain 2845-50
shale	1235	Oil stain 2902-06
lime	1245	Oil stain 2908-18
lime	1490	Oil stain 2928-34
shale & shells	1590	Heebner 2998
lime	1630	Sand 3040-3070
sand	1660	Brown lime 3150-60
lime	1745	Lansing 3178
shale & shells	1995	Porosity 3233-36
shale & shells	2415	Porosity show 3269-74
shale	2570	Porosity show 3286-89
lime brkn	2680	Porosity show 3347-50
lime	3046	Porosity show 3377-81
shale & shells	3155	Porosity show 3401-02
lime	3235	Porous No show 3427-32
lime	3274	Porous No show 3464-68
lime & chert	3323	Mississippi 3600
lime	3432	Dumped 200 Gal. Acid
shale	3441	let set 12 hrs &
lime brkn	3600	bailed 5 gal. oil &
lime cherty	3650	50 gal. wtr 1st hr
shale	3769	2 1/2 gal. oil 2nd hr
lime & shale	3836	Kinderhook 3647
shale	3863	Kinderhook Lime 3740-70
lime	3883	Misener 3862
sand	3931	Viola 3864
shale	3956	Simpson 3885
lime	3984	Arbuckle 3956
Total Depth.		


Plugged back to 3660

Perforations:

3386-3405 20 shots - dry
3241-3250 9 shots - dry
3291-3300 9 shots - wtr
3458-3482 5 shots - dry

D&A - 8-12-42 - Pipe to be
pulled and well to be
plugged at a later date.

10-23-42



PLUGGING

FILE SEC 36 T 22 R 9 W

BOOK PAGE 42 LINE 26