


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Stafford County. Sec. 35 Twp. 24s. Rge. 15w (E) (W)
Location as "NE/CNWxSWx" or footage from lines. CW2 N2 SW4
Lease Owner V. E. Wiggins
Lease Name Barstow B Well No. 1
Office Address P.O. Box 191 Mc Pherson, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed I-29 1960
Application for plugging filed July 1963
Application for plugging approved July 1963
Plugging commenced Aug 7 1963
Plugging completed Aug 17 1963
Reason for abandonment of well or producing formation Went dry

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie Elving
Producing formation Depth to top Bottom Total Depth of Well 4413' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"		3,370'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged off hole with rock. Rock from 3880' to 3800'.
Dumped 5 sx of cement. Mudded hole to 260'. Made 10' of rock bridge. Dumped 20 sx of cement. Mudded hole to 35'. Made 5' of rock bridge. Dumped 10' sx of cement, filling to the bottom of the celler.

RECEIVED
STATE CORPORATION COMMISSION
8-26-63
AUG 26 1963

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Art Lamb Casing Pulling Co.
Address P.O. Box 983 Hutchinson, Kansas

STATE OF Kansas, COUNTY OF Reno, ss.
Art Lamb (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Art Lamb
2809 Kings Dr. Hutchinson, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 22 day of August, 1963

My commission expires January 5, 1966
Notary Public.

Sierra Petroleum Co., Inc. - Operator

WELL #1 - Sold to: V. E. Wiggins - Operator
CN2 H2 S 1/4
35 24S 10W
Stromboli Co., Kansas

Bl. v. 2021' K.D.

Commenced: 1-14-60
Completed: 1-29-60

Casings:

5/8" x 172'
5-1/2" x 4497'

Contents:

w/ 225 sacks
w/ 125 sacks

FORMATION	DEPTH	
Surface Clay & sand	40	
Sand	163	
Shale	272	
Red Bed	944	
Anhydrite	959	
Red Bed & Shale	1436	
Salt Shale	1590	
Shale & shells	1643	
Lime & Shale	3696	
Lime	4054	
Lime & Shale	4161	
Viola	4297	
Simpson	4404	
Arbuckle	4413	
IDs:	Anhydrite	944
	Jobner	3579
	Toronto	3599
	Douglas	3615
	Brown Lime	3727
	Lans. P.C.	3730
	Conglomerate	4030
	Kindershook	4132
	Viola	4161
	Simpson	4297
	Arbuckle	4405
	Total Depth	4413

RECEIVED
STATE CORPORATION COMMISSION

AUG 26 1963

CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
) SS:
COUNTY OF RUSSELL)

I hereby certify that the above information is true and correct to the best of my knowledge.

C. P. Hensler

Subscribed and sworn to before me this 1st day of February, 1963.

Geray Dietz

My commission expires: 10-17-63

3800-5 *ref*

Ref 3808

3860

plus 3880