

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Stafford County. Sec. 35 Twp. 24 Rge. 15 (E) Westw

Location as "NE/CNW&SW" or footage from lines NE NE NE

Lease Owner Helmerich and Payne, Inc.

Lease Name Giles Well No. 1

Office Address 821 Central Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed 1-13 19 56

Application for plugging filed 6-11 19 56

Application for plugging approved 6-12 19 56

Plugging commenced 6-24 19 56

Plugging completed 6-24 19 56

Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production 5-28 19 56

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Russell Brundage

Producing formation Arbuckle Depth to top 4424 Bottom T.D. Total Depth of Well 4437 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Lansing - K.C.	Water	3762		5 1/2"	4426'	3978
Mississippi	Water	4105				
Viola	Water	4192				
Arbuckle	Water & Oil	4424				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plug back with sand to 4410'. Dump 5 sacks cement. Pull 5 1/2" casing. Mud to 215'. Set 5' rick bridge. Mis and dump 20 sacks cement. Fill hole with mud to 35'. Set 5' rock bridge. Mis and put in 10 sacks cement. Fill to base of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Ace Pipe Pulling Co.

Address Great Bend, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

Nathan E. Clark (employee of owner) or ~~(owner or operator)~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Nathan E. Clark

821 Central Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 27th day of June, 19 56

My commission expires Feb. 1, 1960

Barbara J. Layton
Barbara Layton
Notary Public.

6-28-56
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 35 T 24 R 15W
BOOK PAGE 70 LINE 28

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
 508 East Murdock, Wichita, Kansas

Company- HELMERICH & PAYNE, INC.
 Farm- Giles No. 1

SEC. 35 T. 24 R. 15W
 NE NE NE

Total Depth. 4431'
 Comm. 12-20-55 Comp. 1-8-56
 Shot or Treated.
 Contractor. Peel Brothers, Inc.
 Issued. 3-31-56

County Stafford
 KANSAS



Elevation. 2021' KE

Production. 45 BOPD

CASING:

8 5/8" 220'
 5 1/2" 4426'

Figures Indicate Bottom of Formations.

sand	150
shale	390
red rock and shale	965
anhydrite	995
red bed	1825
shale	1930
shale and lime	3825
lime	4075
lime and shale	4125
lime	4190
lime, shale, chert	4262
cherty lime	4405
Simpson	4431
Total Depth	
Tops; Scout	
Heebner	3604
Brown Lime	3752
Lansing	3762
Arbuckle	4424

PLUGGING
 FILE SEC. 35 T. 24 R. 15W
 BOOK PAGE 70 LINE 28

RECEIVED
 GEOLOGICAL COMMISSION

APR 1 1956