

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, Kansas 67202

Well Plugging Record
K.A.R. -82-3-117

API NUMBER 15-185-230310000
LEASE NAME Scott
WELL NUMBER 1-35

TYPE OR PRINT

NOTICE: Fill out completely and return
to Cons. Div. office within 30 days.

2970 Ft. from S / N Line of Section (Circle one)
3960 Ft. from E W Line of Section (Circle one)

LEASE OPERATOR F.G. Holl Company, L.L.C. SPOT LOCATION C - S/2 - S/2 - NW
ADDRESS 6427 E. Kellogg, P.O. Box 780167 Section 35 Township 24 Range 15w
CITY, STATE, ZIP Wichita Kansas 67278-0167 County Stafford
PHONE # (316) 684-8481 Date Well Completed August 22 1996
Character of Well Dry and Abandoned Date Plugging Commenced August 22 1996
(Oil, Gas, (D&A), ISWD, Input, Water Supply Well) Date Plugging Completed August 22 1996

The plugging proposal was approved on August 16, 1996 (date)
by Steve Middleton (KCC District Agent's Name)

Is ACO-1 Filed? ? If not, is well log attached? Yes
Producing Formation(s) D&A Depth to Top Bottom T.D. 4461

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
Surface Soil and Sands	Water sands	0	170	and		
Shale	Shale	170	235	8-5/8"	218.47	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Heavy mud to 980' then 50 sacks, heavy mud to 260' then 40 sacks, heavy mud to 40' then 10 sacks. Using 60/40 Poz with 6% Gel. Plug rathole with 15 sacks and plug mousehole with 10 sacks.

(If additional description is necessary, use BACK of this form)

Name of Plugging Contractor Sterling Drilling Company
Licence No. 5142
Address P.O. Box 1006 City: Pratt State: Kansas Zip 67124
NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: F.G. Holl Company, L.L.C. (Operator)

STATE OF KANSAS COUNTY OF PRATT, ss.

Steve E. McClain, Agent (Employee of Operator or (Operator) of above described well, being first
duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of
the above described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]
(Steve E. McClain, President of Sterling Drilling Company)

(Address) P.O. Box 1006 City: Pratt State: Kansas Zip 67124

SUBSCRIBED AND SWORN TO me this 27th day of August, 1996



[Signature]
(Notary Public)

RECEIVED
KANSAS CORPORATION COMMISSION
AUG 29 1996
8-29-96
CONSERVATION DIVISION
WICHITA, KS

My Commission Expires: _____

Sterling Drilling Company, Rig #4

Box 1006, Pratt, Kansas 67124-1006

Office Phone (316) 672-9508, Fax 672-9509

SAMPLE LOG

API# 15-185-23031,0000

Scott 1-35

LOCATION: C S/2 S/2 Nw

Section 35 T 24s R 15W
Stafford County, Kansas

OWNER: F.G. Holl Company L.L.C.

COMMENCED: 13-Aug-96

CONTRACTOR: Sterling Drilling Company, Rig #4

COMPLETED: 22-Aug-96

TOTAL DEPTH: DRILLER 4461 FEET

ELEVATIONS: G.L. 2021

LOGGER 4458 FEET

K.B. 2030

LOG

0 -	170 FEET	Surface soil and sand
170 -	235 FEET	Shale
235 -	1126 FEET	Shale and Redbeds
1126 -	1144 FEET	Anhydrite
1144 -	3450 FEET	Lime/Shales/Dolomite

Note: Lost some mud volume at 1200'.

CASING RECORDS

Spud @ 7:45 am on 8-13-96. Drilled 235' 12-1/4" hole, ran 5 jts 23# 8-5/8" casing. 218.47' set at 230' KB. Cement with 180 sx. 60/40 Poz, 2% Gel, 3% CC. Plug down at 11:00 am on 8-13-96 by HOWCO, Ticket # 968610. Good Returns.

Received plugging orders on 8-16-96 from Steve Middleton. Started plugging at 3:00 am on 8-22-96. Plugged using 60/40 Poz and 6% Gel as follows: 50 sacks at 980', 40 sacks at 260', 10 sacks at 40', 15 sacks in rathole, 10 sacks in mousehole. Plug down at 5:00 am on 8-22-96. Plugged by HOWCO, ticket # 968616.

DEVIATION SURVEYS

1/4 DEG. @	235 FEET
3/4 DEG. @	2694 FEET
1 DEG. @	3130 FEET
1.25 DEG. @	4421 FEET

RECEIVED
KANSAS CORPORATION COMMISSION

AUG 29 1996

CONSERVATION DIVISION
WICHITA, KS