

STATE OF KANSAS
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Stafford

County. Sec. 26 Twp. 24 Rge. 15 (E) W (W)

NORTH



Locate well correctly on above
Section Plat

Location as "NE/CNW/SW" or footage from lines SE SE SE
Lease Owner Lewis Drilling Company
Lease Name Blount Well No. 1
Office Address Ellinwood, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil Well
Date well completed 10-1 19 55
Application for plugging filed _____ 19 _____
Application for plugging approved _____ 19 _____
Plugging commenced 9-16 19 57
Plugging completed 9-25 19 57
Reason for abandonment of well or producing formation Became non-commercial

If a producing well is abandoned, date of last production 8-30 19 57
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well R. M. Brundege
Producing formation Arbuckle Depth to top 4413 Bottom _____ Total Depth of Well 4428 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	200'	none
				5 1/2"	4416'	3684'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked the hole to 4425' and found it open.
Filled w/sand to 4410' and ran 5 sacks of cement. Pulled 5 1/2" casing with the exception of 16 jts. pumped in 26 sacks gel mud and pulled final 16 jts. Could not bail fluid down, so pushed plug to 205', set a rock bridge and ran 25 sacks of cement. Mudded hole to 30', set a rock bridge and ran 10 sacks of cement to base of cellar.

10-29-57
OCT 29 1957
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor West Supply Co., Inc.
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Rice, ss.
J. Fred Hambright (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. Fred Hambright
(J. Fred Hambright)
915 Union Center, Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 9 day of October, 19 57

A. R. Derrington
(A. R. Derrington) Notary Public.

My commission expires 8-20-60

PLUGGING
FILE SEC 26 T 24 R 15 W
BOOK PAGE 46 LINE 1


WELL LOG

COMPANY **Lewis Drilling Company, et al**
 FARM **B. N. Elcomb** NO. **1**

SEC. **26** T. **24** R. **15W**
 LOC. **S1/4S1/4E1/4**

TOTAL DEPTH **1428**
 CORR. **9-7-55** COMP. **9-22-55**
 SHOT OR TREATED
 CONTRACTOR **Lewis Drilling Company**
 ISSUED

COUNTY **Stafford**
KANSAS



ELEVATION **2018 22**

PRODUCTION

CASINO

20 **X¹⁰ 8-5/8" 209'**
 15
 12 **X⁶ 5-1/2" 1126'**
 13

FIGURES INDICATE BOTTOM OF FORMATIONS

0 - 140	Sand and gravel.
140 - 160	Clay
160 - 285	Blue shale
285 - 965	Red beds and shale
965 - 999	Anhydrite
999 - 1820	Shale and red beds
1820 - 2025	Shale and lime streaks
2025 - 3290	Lime and shale
3290 - 3480	Lime
3480 - 3594	Lime and shale
3594 - 3600	Heebner shale
3600 - 3840	Lime and shale
3840 - 3877	Lime
3877 - 3900	Lime and shale
3900 - 4124	Lime
4124 - 4295	Lime and chert
4295 - 4307	Chert
4307 - 4398	Shale, sand, and lime
4398 - 4413	Lime and shale
4413 - 4428	Arbuckle Lime
4428	T.O.

GEOLOGIC TOPS

Heebner	3594'	(-1576)
Douglas	2633'	(-1615)
Br. Lime	3743'	(-1725)
K. C.	3758'	(-1740)
Base K. C.	4012'	(-1994)
Miss.	4123'	(-2105)
Viola	4186'	(-2168)
Stinson	4329'	(-2311)

PLUGGING

FILE SEC. 26 T. 24 R. 15W

BOOK PAGE 46 LINE 1

RECEIVED
 STATE CORPORATION COMMISSION
 SEP 17 1957
 CONSERVATION DIVISION
 Wichita, Kansas

State of KANSAS
 County of SEDMICK } ss:

I, J. Fred Hanbright of the Lewis Drilling Company

upon oath state that the above and foregoing is a true and correct copy of the log of the B. N. Elcomb #1 well.

Subscribed and sworn to before me this 26th day of September 1955

My Commission Expires: August 20, 1956

(Signature)
Arthur R. Derrington
(Arthur R. Derrington)