

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-185-21,650-A

LEASE NAME Blount

WELL NUMBER #1

SPOT LOCATION E/2-E/2-NE

SEC. 26 TWP 24 RGE. 15 (E) or (W)

COUNTY Stafford

Date Well Completed _____

Plugging Commenced 3-28-86

Plugging Completed 4-4-86

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR John J. Darrah, Jr.
412 E. Douglas, Suite One
ADDRESS Wichita, Kansas 67202

PHONE # (316-263-2243) OPERATORS LICENSE NO. 5088

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? One (1)

Is ACO-1 filed? _____ If not, is well log attached? With application

Producing formation _____ Depth to top _____ bottom T.D. 4310'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	303'	None
				4-1/2"	4287'	2,055.23'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.
Dumped sand to 4100' and 4 sacks cement. Shot casing at 3000', 2500', 2300' and 2100'. Pulled 49 joints of 4-1/2" casing. Halliburton squeezed well with 3 sacks hulls and 120 sacks 60/40 pozmix cement with 10% added gel, 2% Econ-lite and 1/4 pound Floseal per sack, blended with 2 sacks hulls.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111
Address Box 698, Great Bend, Ks. 67530

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold
(Address) Box 698, Gr. Bend, Ks. 67530

Recd
APR - 8 1986
4-8-86
CONSERVATION DIVISION
Wichita, Kansas

SUBSCRIBED AND SWORN TO before me this 7th day of April, 1986

STATE NOTARY PUBLIC
IONA M. LEATHERMAN
Barton County, Kansas
My Appt. Exp. 9-26-87

Iona M. Leatherman
Notary Public

My Commission expires: