

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
30 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-185-21, 513-0000  
LEASE NAME Cummins  
WELL NUMBER 3-15

TYPE OR PRINT  
NOTICE: Fill out completely and return  
to Cons. Div. office within 30 days.

3960 Ft. from (N) Line of Section (circle one)  
990 Ft. from (E) Line of Section (circle one)

LEASE OPERATOR F. G. Holl, L. L. C.  
ADDRESS 6427 E. Kellogg P.O. Box 780167  
CITY, STATE, ZIP Wichita KS 67278-0167  
PHONE# (316) 684-8481 OPERATORS LICENSE NO. 5056  
Character of Well Oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

SPOT LOCATION E - C - N.E.  
SEC. 15 TWP. 24 S. RGE 15 (E) or (W)  
COUNTY Stafford  
Date Well Completed \_\_\_\_\_  
Date Plugging Commenced 3-31-97  
Date Plugging Completed 5-16-97

The plugging proposal was approved on 3-12-97 (date)  
by Steve Pfeifer (KCC District Agent's Name)  
Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing Formation(s) \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4240  
PBTD 4175  
Show depth and thickness of all water, oil and gas formations. PERFS. 4148-52

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PWT IN	PULL OUT
	Surface	0	265	8 5/8	265	0
	Casing	0	4239	4 1/2	4239	2070'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

3-31-97 Traced sand 4050 down from surface 4-1-97 Dumped 45x cement on top of sand. Shot off casing 2070' 4-2-97 Laid down total of 51 jts. Rigged down & moved off. 5-16-97 Halliburton pumped 300# hulla, 10 gel, 50 cement, 10 gel, 100# Hulla, 175 5x cement, 8 5/8 plug. (If additional description is necessary, use BACK of this form.) I.S.I.P. 250 lbs.

Name of Plugging Contractor Pratt Well Service Inc.

License No. 5893

Address Box 847 Pratt, KS 67124

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: H. R. Holl

STATE OF Kans COUNTY OF Pratt ss.

Stephen E. Hart (Employee of Operator or (Operator) of above-described well, being first

sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Stephen E. Hart

(Address) c/o P.O. S. Inc.

SUBSCRIBED AND SWORN TO before me this 23rd day of July, 1997

Kenneth W. Furgason Notary Public

My Commission Expires:  KENNETH W. FURGASON  
Notary Public - State of Kansas  
My Appl. Expires 06/19/00

Rec'd  
7-26-97  
RECEIVED  
KANSAS CORP COM  
1997 JUL 26 4 12 05