

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Stafford SEC. 15 TWP. 24S RGE. 15W E/W
Location as in quarters or footage from lines:

C SW NE

Lease Owner F. G. Holl
 Lease Name Cummins #6-15 Well No. #6-15
 Office Address 6427 East Kellogg, Wichita, Kansas 67207
 Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
 Date Well Completed July 10, 1982
 Application for plugging filed July 10, 1982
 Plugging commenced 6:15 PM, July 10, 1982
 Plugging completed 9:45 PM, July 10, 1982
 Reason for abandonment of well or producing formation Dry Hole

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Paul Luthie

Producing formation _____ Depth to top _____ bottom _____ T.D. 4235'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	263'	None

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Filled hole with heavy mud.
Plugged through open ended drill pipe -
60 sacks at 720'; 35 sacks at 300';
10 sacks at 40' with 1/2 sack hulls, plug,
bridge; 10 sacks in rathole with jt. of
drill pipe. 3 sacks in water well.

RECEIVED
 STATE CORPORATION COMMISSION
 7-14-82
 JUL 14 1982
 CONSERVATION DIVISION
 Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sterling Drilling Company, P. O. Box 129, Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE, ss.
F. A. Wuellner (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

STERLING DRILLING COMPANY
 (Signature) [Signature]
F. A. Wuellner, Secretary
P. O. Box 129, Sterling, Kansas 67579
 (Address)

SUBSCRIBED AND SWORN TO before me this 12th day of July, 19 82.



[Signature]
 Agnes D. Wurst, Notary Public.

My Commission expires: _____

STERLING DRILLING CO.

BOX 129

STERLING, KANSAS 67579

WELL LOG - - - - - CUMMINS #6-15

Located: C SW NE, Section 15-24S-15W, Stafford County, Kansas

OWNER: F. G. Holl

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: July 2, 1982

COMPLETED: July 10, 1982

TOTAL DEPTH: 4235

<u>LOG</u>	<u>CASING RECORD</u>
0 - 40 Surface Soil and Sand	Ran 6 joints 8 5/8", 24# new casing.
40 - 266 Shale	250.97' pipe set at 263' K.B. Cemented with 210 sacks 60/40 Pozmix with 3% cc. Plug down at 11:30 AM, 7-2-82, by Howco.
266 - 734 Shale and Sand	
734 - 968 Shale and Red Beds	
968 - 983 Anhydrite	
983 - 1530 Shale and Shells	
1530 - 4120 Lime and Shale	
4120 - 4185 Arbuckle, Kinderhook Sand and Simpson Sand	
4185 - 4235 Lime and Shale	Plugged.

RECEIVED
STATE CORPORATION COMMISSION

JUL 14 1982

CONSERVATION DIVISION
Wichita, Kansas

Deviation Surveys: 1° at 2062'
1 1/2° at 3867'