

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Stafford SEC. 15 TWP. 24S RGE. 15W E/W  
Location as in quarters or footage from lines:  
SE NE NW


Locate Well  
correctly on above  
Section Platt.

Lease Owner F. G. Holl  
Lease Name Biggs Well No. 1-15  
Office Address 6427 East Kellogg, Wichita, Kansas 67207  
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole  
Date Well Completed January 30, 1984  
Application for plugging filed January 30, 1984  
Plugging commenced 6:15 PM, January 30, 1984  
Plugging completed 7:30 PM, January 30, 1984  
Reason for abandonment of well or producing formation Dry Hole

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Paul Luthie  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom T.D. 4242'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	260'	None

Describe in detail the manner in which the well was plugged, indicating where the mud  
fluid was placed and the method or methods used in introducing it into the hold. If cement  
or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy mud,  
Plugged through open ended drill pipe  
50 sacks at 4020'; 50 sacks at 970';  
50 sacks at 300'; 1/2 sack Halls, plug and  
10 sacks at 40'. 15 sacks in rathole with  
jt. of drill ippe. Did not plug water well.  
Used 60/40 Pozmix plus 2% gel (total of 4%).

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sterling Drilling Company, P. O. Box 129, Sterling, Kansas 67579


STATE OF KANSAS COUNTY OF RICE, ss.  
F. A. Wuellner (employee of owner) or (owner or operator) of the  
above-described well, being first duly sworn on oath, says: That I have knowledge of the  
facts, statements, and matters herein contained and the log of the above-described well as  
filed and that the same are true and correct. So help me God

(Signature) [Signature]  
F. A. Wuellner, Secretary  
(Address)  
P. O. Box 129, Sterling, Ks. 67579

SUBSCRIBED AND SWORN TO before me this 31st day of January, 1984.

[Signature]  
Agnes D. Wurst, Notary Public.

My Commission expires: 4-6-85



RECEIVED  
STATE CORPORATION COMMISSION  
2-2-84  
FEB 02 1984  
2-02-84  
CONSERVATION DIVISION  
Wichita, Kansas

# STERLING DRILLING CO.

BOX 129

STERLING, KANSAS 67579

WELL LOG - - - - - BIGGS #1-15  
Located: SE NE NW, Section 15-24S-15W, Stafford County, Kansas

OWNER: F. G. Holl

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: January 23, 1984

COMPLETED: January 30, 1984

TOTAL DEPTH: 4242'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 75 Surface Soil and Sand	Ran 6 joints new 8 5/8", 24# casing. 247.57' pipe set at 260' K.B.
75 - 100 Clay	Cemented with 210 sacks 60/40 Pozmix with 3% cc. Plug down at 7:45 PM, 1-23-84, by Howco.
100 - 263 Shale	
263 - 770 Shale, Sand, Red Beds	
770 - 1800 Shale and Lime Stringers	
1800 - 4242 Lime and Shale	Plugged.

Deviation Surveys: 1 3/4° at 2152'  
1 1/2° at 4121'