

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-185-21159-0000

LEASE NAME CUMMINS

WELL NUMBER 1-15

TYPE OR PRINT
NOTICE: Fill out completely and return
to Cons. Div. office within 30 days.

3300 Ft. from SR Line of Section (circle one)

660 Ft. from EW Line of Section (circle one)

LEASE OPERATOR F. G. Holl Company, L.L.C

ADDRESS 6427 E. Kellogg P.O.Box 780167

CITY, STATE, ZIP Wichita, Kansas 67278-0167

PHONE# (316) 995-3171 OPERATORS LICENSE NO. 5056

Character of Well Oil Well
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

SPOT LOCATION C - SE - NE

SEC. 15 TWP. 24S S. RGE 15 KEY or (W)

COUNTY Stafford

Date Well Completed _____

Date Plugging Commenced Sept. 15, 1997

Date Plugging Completed Sept. 16, 1997

The plugging proposal was approved on September 8, 1997 (date)

by Mr. Richard Lacey (KCC District Agent's Name)

Is ACO-1 filed? Yes If not, is well log attached? Yes

Producing Formation(s) Stone Corral Formation Depth to Top _____ Bottom 4224' T.D. 4273'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
	Surface	0	343'	KB 8 5/8"	343'	0
	Prod. Casing	0	4268'	KB 4 1/2"	4268'	2005'

Described in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Dumped 4 sxs cement on top of sand, 300 lbs. Hulls, 10sxs Gel @ 8.9 ppg. 50 sxs.

cmt @ 12.8 ppg., 10 sxs Gel @ 8.9 ppg, 100 lbs. Hulls, Release wooden plug.

125 sxs. Cmt @ 12.8 ppg. Total Bbls. pumped - 120.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Pratt Well Service Inc.

License No. 5893

Address P. O. Box 847 Pratt, Kansas 67124

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: F. G. Holl Co. L.L.C.

STATE OF Kansas COUNTY OF Edwards, ss.

Stephen E. Hart - Office Mang. (Employee of Operator or (Operator) of above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Stephen E. Hart

(Address) C/O Pratt Well Service Inc. Box 847 Pratt, Ks. 67124

SUBSCRIBED AND SWORN TO before me this 30th day of September, 1997

Kenneth W. Furgason
Notary Public

My Commission Expires: 06/19/00

KENNETH W. FURGASON
Notary Public - State of Kansas
My Appt. Expires 06/19/00

Form CP-4
Revised 12-97

RECEIVED
KANSAS CORP CO
1997 OCT -1 12:54
Rec'd
10-1-97