


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Stafford County. Sec. 21 Twp. 24S Rge. 15W E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
SE SE NW

Lease Owner Zenith Drilling Corporation, Inc.
Lease Name Holcomb #1 Well No. 1
Office Address Suite 600, 200 West Douglas, Wichita, Ks 67202
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above
Section Plot

Dry Hole
Date Well completed August 2, 1978 19
Application for plugging filed August 2, 1978 19
Application for plugging approved August 2, 1978 19
Plugging commenced 1:30 PM August 2, 1978 19
Plugging completed 3:15 PM August 2, 1978 19
Reason for abandonment of well or producing formation

Dry Hole
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bill Owen
Producing formation Depth to top Bottom Total Depth of Well 4265'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	294'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud.
Pumped thru open ended O.D. 50 sacks at 540' and 40 sacks at 290'. Solid Bridge at 40' with 1/2 sack hulls and plug with 12 sy to surface. 3 sacks in rathold. Used 50/50 Pozmix cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sterling Drilling Company
P. O. Box 129, Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE ss.
F. A. Wuellner

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. STERLING DRILLING COMPANY

(Signature) *F. A. Wuellner*
F. A. Wuellner, Secretary
P. O. Box 129, Sterling, Kansas 67579
(Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of August 1978



Charles M. Hall
Charles M. Hall, Notary Public.

STATE CORPORATION COMMISSION
8-7-78
AUG 07 1978

CONSERVATION DIVISION
Wichita, Kansas

STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579

WELL LOG - - - - - HOLCOMB #1
Located: SE SE NW, Section 21-24S-15W, Stafford County,
Kansas

OWNER: Zenith Drilling Corporation, Inc.
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: July 28, 1978
COMPLETED: August 2, 1978

TOTAL DEPTH: 4265'

LOG

0 - 212 Sand and Clay
212 - 445 Clay and Shale
445 - 1006 Shale, Sand and Red Bed
1006 - 1022 Anhydrite
1022 - 1780 Shale
1780 - 2114 Shale and Lime
2114 - 2332 Shale and Lime Stgrs.
2332 - 4030 Shale and Lime
4030 - 4265 Lime

CASING RECORD

Ran 7 joints new 23#, 8 5/8" casing,
282.29' set at 294' K.B. with 225
sacks 60/40 Pozmix with 3% cc. Plug
down at 1:30 PM, 7-28-78, by Howco.

Plugged.

RECEIVED
STATE COMMISSION

AUG 07 1978

CONSERVATION
Wichita