

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

DEC 2 1963
 17-2-63
 CONSERVATION DIVISION
 Wichita, Kansas

Dear Sir:

Mr. T. F. Brown of Gabbert-Jones Inc. has this

date requested permission to plug the following described well:

Mr. Brown guarantees payment of the plugging fee.

Operator's full Name: Dianne McCarthy

Complete Address: 407 Insurance Bldg., Wichita, Kansas

Lease Name: Fritzemeyer Well No. # 1

Location: SW SW NW Sec. 3 Twp. 24 Rge. 12 (E) (W) W

County Stafford Total Depth 3995 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Brown was instructed to plug the well as follows:

205' of 8 5/8" surface pipe, cemented with 210 sacks.

Fill hole with drilling mud to 250', 1st cementing plug,

1/4 sack hulls, cement with 30 sacks. Fill hole with drill-

ing mud to 40', 2nd cementing plug, 1/4 sack hulls, cement

with 10 sacks to base cellar. Bridge and cement rat hole
with 2 sacks.

Very truly yours,

Archie Elving
 Conservation Division Agent