

State of Kansas



FORM - GP-2
Rev. 9-8-64

15-155-20033-0000

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

November 4, 1967

RECEIVED
NOV 7 1967
11-7-67
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Robert Miller of Graves Drilling Co., Inc. has this

date requested permission to plug the following described well:

Mr. Miller guarantees payment of the plugging fee.

Operator's full Name: Jay-Bee Oil Company, Inc.

Complete Address: 515 Union Center, Wichita, Kansas 67202

Lease Name: Sleeper "B" Well No. 1

Location: Sec. 25 Twp. 22 Rge. 10 (N) (W) X

County Reno Total Depth 3735' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Miller was instructed to plug the well as follows:


Fill hole with mud to 225'. Push plug and $\frac{1}{4}$ sack hulls to 225' and

cement hole with 25 sacks through drill pipe. Fill hole with mud to

40'. Push plug and $\frac{1}{2}$ sack hulls to 40' and cap hole with 10 sacks

cement. Bridge rathole, and cement with 2 sacks.

Very truly yours,


Conservation Division Agent