



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water
WICHITA, KANSAS 67202

March 25, 1977

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

APR 07 1977
4-7-77
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Bill Chance of Rains & Williamson Oil Co. has this
date requested permission to plug the following described well:

Mr. Chance guarantees payment of the plugging fee.

Operator's full Name: Rains & Williamson Oil Co., Inc.

Complete Address: 435 Page Court-220 W. Douglas, Wichita, Kansas

Lease Name: Sleeper Well No. 1

Location: NW NW SE Sec. 25 Twp. 22 Rge. 10 (E) (W) X

County: Reno Total Depth 3730' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Chance was instructed to plug the well as follows:

Fill hole with mud. Pump 40 sacks cement through drill pipe

at 500'. Pump 25 sacks cement through drill pipe at 240'.

Push plug and $\frac{1}{2}$ sack hulls to 40' and cap hole with 10 sacks

cement. Bridge rathole and cement with 2 sacks cement.

Very truly yours,

[Signature]
Conservation Division Agent