

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS

JEWEL M. OGDEN, Director

GEORGE DOCKING Governor  
MARION BEATTY Chairman  
HARRY G. WILES Commissioner  
RICHARD C. BYRD Commissioner  
RAYMOND B. HARVEY Secretary  
CLYDE E. MILLIGAN Counsel

Jewel M. Ogden, Director.  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

I have this date 6 September, 1958, authorized the following plugging operation:

Operator's Full Name: Osage Oil & Gas Co.

Complete Address: 523 Petroleum Bldg., Wichita, Kans.

Lease Name: Teichman Well No. 1

Location: NE NE NW Sec. 17 Twp. 24 Rge. 12 (E) (W) X

County: Stafford Total Depth: 4100

Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated:       

Operator was instructed to plug well as follows:

268' of 8 5/8" surface casing circulated with cement. Fill  
hole to 250' with heavy drilling mud. Place cementing plug and  
1/2 sack balls at 250' with 20 sack cement top plug. Fill hole  
to 35' with heavy drilling mud. Place cementing plug and cement  
to base of cellar.

Very truly yours,

Signed: [Signature]  
Conservation Division Agent

RECEIVED  
STATE CORPORATION COMMISSION  
9-20-58  
SEP 20 1958  
CONSERVATION DIVISION  
Wichita, Kansas