

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAY 23 1966
5-23-66
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Dean Nossaman of Stickle Drilling Company has this date requested permission to plug the following described well:

Mr. Nossaman guarantees payment of the plugging fee.

Operator's full Name: Stickle Drilling Company

Complete Address: 1100 Bitting Bldg., Wichita, Kansas

Lease Name: Byer Well No. # 2

Location: NW SE NE Sec. 21 Twp. 24 Rge. 12 (E)(W) W

County Stafford Total Depth 3939' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Nossaman was instructed to plug the well as follows:

247' of 8 5/8" surface pipe, cement circulated with 260 sacks. Fill hole with drilling mud to 230', 1st cementing plug, bridge with 1/2 sack of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10 sacks to base of cellar. Bridge and cement rat and mouse holes with 4 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent