

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
3-1-72
MAR 1 1972
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Barnett Oil Co.

Complete Address 411 1st Natl Bldg. Wichita, Ks

Lease Name Teichman Well No. 1

Location C S/2 NE/NW Sec. 17 Twp. 24 Rge. 12 (E) (W) W

County Stafford Total Depth 3873

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Santa Fe Pipe & Supply Co. Inc.

Address Box 562 Great Bend, Ks License No. 574

Operation Completed: Hour 11:00 AM Day 28 Month 2 Year 1972

The above well was plugged as follows:

196 ft 8 5/8 surface pipe cemented with 200 sacks. 3871 ft 4 1/2 long
string cemented with 125 sacks. Push plug to 3800 ft. Sand & 4 sacks
cement with bailer. Pulled 2000 ft 4 1/2. Pump 2 sacks hulls, 15 sacks
gel & 100 sacks cement to surface.

Pumped by Halliburton Cementing Co. Great Bend, Ks

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 3/1/72
INV. NO. 5256-4