

*J*  
KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

5-24-65  
MAY 24 1965

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Columbia Drilling Company

Complete Address: 139 N. Mead, Wichita, Kansas

Lease Name Byer Well No. # 1

Location CEL NW SE Sec. 17 Twp. 24 Rge. 12 (E) (W) W

County Stafford Total Depth 3889'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Knight Casing Pulling Company

Address: Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 6:00 PM Day 21st Month May Year 1965

The Above well was plugged as follows:

286' of 8 5/8" surface pipe, cement circulated. 3886' of 5 1/2" long string,  
cemented with 75 sacks. Top perferation 3870'. Bottom of the hole was  
sanded to 3860', and cemented with 5 sacks. 2991' of 5 1/2" long string was  
recovered from the hole. Fluid in the hole was bailed down to 285',  
bridge plug set on fluid at 285', and 10' of rock bridge, and cemented  
with 20 sacks. Hole was filled with mud to 40', and 10' of rock bridge,  
and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 5/24/65

INV. NO. 1209-W

Signed: Archie Elving  
Well Plugging Supervisor