

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 42-44

LOCATION E/2-SW-NE

SEC. 15 TWP. 24 RGE. 15-W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 2 Lease C. Crawford

Operator Stanwood Oil & Gas Co Address Box #7, Elliswood - Kans.

Field _____ County Stafford

Total Depth 3847 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 3/8 - 250 ft. Circulated with cement
1 1/2 casing set at 3819 - Cemented with 100 sacks cement
Plugged back to 3810 ft with chat - Dumped 5 sacks
of cement at 3810 ft - Shot off & pulled the casing
filled hole with sand to 250 ft - Set Rock Bridge &
15 sacks of cement at 250 ft - Mud to 30 ft - Plug
X 10 sacks of cement at the surface -
Chambers Pipe Pulling Co - Plugging Dept

STATE CORPORATION
NOV 27 1950 11-27-50
CONSERVATION DIVISION
Wichita, Kansas
W. O'Boyle

District Conservation Agent

Date 11-23-50

PLUGGING
FILE SEC 15 T 24 R 12W
BOOK PAGE 42 LINE 44