

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 9-38

LOCATION C7 1/2 - SW - SE

SEC. 16 TWP. 24 RGE. 12W

Dry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 4 Lease R. Charles, "B"

Operator Standard Oil & Gas Co Address Box #7 - Ellinwood - Kans.

Field \_\_\_\_\_ County Stafford

Total Depth 3946 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 3/4 - 253 ft - Circulated with cement  
5 1/2 casing at 3940 - Plugged back to 3475 ft  
with mud - Baker Plug & cement - Pumped 5 sacks  
of cement at 3475 ft - Ripped off & pulled the 5 1/2 casing -  
filled with mud to 253 ft - Rock Bridge & 15 sacks  
of cement at 253 ft - Mud to 30 ft - Bridge &  
10 sacks of cement at the surface -  
Bill Morgan - Plugging Contractor

JUN 14 1950

Conservation  
District Conservation Agent

Date 6-10-50

**PLUGGING**  
FILE SEC 15 T 24 R 12 W  
PAGE 9 LINE 38