


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Stafford County. Sec. 7 Twp. 24S Rge. 12W ~~12E~~ (W)
Location as "NE/CNW/SW" or footage from lines SW/4 NE/4 SE/4
Lease Owner Barnett Oil Company
Lease Name O'Connor "B" Well No. 1
Office Address 411 First National Bank Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed March 27, 1962
Application for plugging filed May 2, 1962
Application for plugging approved May 2, 1962
Plugging commenced May 2, 1962
Plugging completed May 7, 1962
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Lackamp, R.R. #1, Stafford, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3885 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|-----------|------------|
| | | | | 8 5/8" | 215' | -0- |
| | | | | 4 1/2" | 3875 1/2' | 3239' |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Cleaned out cellar. Set unit, rigged up and had water truck load hole. Sanded back to 3860' and dumped 4 sacks cement. Rigged up jacks and spiders and took pipe off head. Worked pipe and cleaned hole for shot. Shot well @ 3223'. Worked pipe and started laying down casing. Laid down 50 jts. wet string. Finished laying down casing. Bailed down hole from 50' to 200'. Dug pit by hand to hold fluid. Set 10' rock bridge @ 200' with 20 sacks cement. Tallied pipe. Mudded hole from 130' to 40'. Set 10' rock bridge with 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
MAY 11 1962
CONSERVATION DIVISION
Wichita, Kansas

(Well Log attached)

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Forbes Casing Pulling, Inc.
Address Box 221, Great Bend, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.
F. H. Rousey, Office Manager, (employee of owner, operator or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) F. H. Rousey
411 First Nat'l Bank Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of May, 1962

My commission expires February 27, 1964. Mildred F. Willis Notary Public.



BARNETT OIL COMPANY
 WELL LOG - O'CONNOR "B" #1
 SW/4 NE/4 SE/4 SECTION 7-24S-12W
 STAFFORD COUNTY, KANSAS

| <u>From</u> | <u>To</u> | <u>Formation</u> |
|-------------|-----------|---|
| 0 | 40 | Surface Sand |
| 40 | 70 | Sand and Clay |
| 70 | 130 | Clay |
| 130 | 145 | Sand |
| 145 | 215 | Shale |
| 215 | 635 | Shale and Red Bed |
| 635 | 695 | Red Bed |
| 695 | 725 | Anhydrite |
| 725 | 1335 | Shale and Shell |
| 1335 | 1865 | Shale and Lime |
| 1865 | 2410 | Lime and Shale |
| 2410 | 3250 | Shale and Lime |
| 3250 | 3595 | Lime and Shale |
| 3595 | 3877 | Lime (T.D.) - Rotary |
| 3877 | 3885 | Lime (Drilled with Cable Tools) (D. & A.) |

Set 8 5/8", 28# used casing
 at 215' with 200 sacks.

Set 4 1/2", 9.50# new casing
 at 3875 1/2' with 125 sacks.

Pulled 4 1/2" pipe and plugged.
 D. & A.

RECEIVED
 STATE CORPORATION COMMISSION

OCT 11 1962

CONSERVATION DIVISION
 Wichita, Kansas