

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

Stafford

County. Sec. 17 Twp. 24 Rge. (E) 12 (W)

Location as "NE/CNW/SW" or footage from lines. A/C S/2 NE/4 NW/4

Lease Owner Barnett Oil Company

Lease Name Teichman

Well No. 1

Office Address 411 First National Bank Bldg., Wichita, Kansas 67202

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed August 29, 1961

Application for plugging filed February 17, 1972

Application for plugging approved February 18, 1972

Plugging commenced February 28, 1972

Plugging completed February 28, 1972

Reason for abandonment of well or producing formation Non-Commercial

If a producing well is abandoned, date of last production February 17, 1972

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well G. Russell Biberstein

Producing formation Viola Depth to top 3870 Bottom 3873 Total Depth of Well 3873 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	196'	-0-
				4 1/2"	3871'	1995'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Mixed 2 sacks hulls and 15 sacks gel pumped into surface pipe by Halliburton.  
Topped with 100 sacks cement; completed @ 11:30 A.M., 2-28-72.

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 22 1972  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Santa-Fe Pipe & Supply, Inc.

Address Box 562 - Great Bend, Kansas 67530

STATE OF Kansas, COUNTY OF Sedgwick, ss.

Jack S. Griggs, a partner

(operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jack S. Griggs

411 First Nat'l Bank Bldg., Wichita, Ks. 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of February, 1972.

Mildred F. Willis  
Mildred F. Willis, Notary Public.

My commission expires February 27, 1976.



WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas


COPY

Company. BARNETT OIL CO.  
Farm. Teichman No. 1

SEC. 17 T. 24 R. 12W  
C S/2 NE NW

Total Depth. 3873'  
Comm. 8-21-61 Comp. 9-10-61  
Shot or Treated.  
Contractor.  
Issued. 1-13-61

County Stafford  
KANSAS



Elevation. 1890' RB

Production. 36 BOPD

CASING:

8 5/8" 196' cem w/200 sx.  
4 1/2" 3871' cem w/125 sx.

Figures indicate Bottom of Formations.

surface clay	40
sand	80
sand, shale	150
shale & shell	196
shale	580
shale & red bed	705
Anhydrite	730
shale & shell	1130
shale	1750
shale & lime	1840
lime	2020
lime & shale	3225
lime	3290
lime & shale	3545
lime	3873
Total Depth	

TOPS: SCOUT	
Heebner	3327
Brown Lime	3480
Kansas City	3508
Base Kansas City	3730
Viola	3870

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 18 1972  
CONSERVATION DIVISION  
Wichita, Kansas