

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Stafford SEC. 17 TWP. 24S RGE. 12 E/W  
Location as in quarters or footage from lines:  
100' W of C W/2 NE SE


Lease Owner Landmark Oil Exploration  
Lease Name Byer Well No. #1  
Office Address 105 S. Broadway - Suite 730 Wichita, Ks. 67202  
Character of Well (Completed as Oil, Gas or Dry Hole): Dry  
Date Well Completed 9-11-83  
Application for plugging filed 9-11-83  
Plugging commenced 9-11-83  
Plugging completed 9-11-83  
Reason for abandonment of well or producing formation \_\_\_\_\_

Locate Well  
correctly on above  
Section Platt.

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well J. H. Metz  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 3925'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	324'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud  
fluid was placed and the method or methods used in introducing it into the hold. If cement  
or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
to \_\_\_\_\_ feet for each plug set.

Spotted 20 sx. cement @ 750' thru drill pipe.  
Spotted 70 sx. cement @ 350' thru drill pipe.  
Solid bridge plug set @ 40', Spotted 10 sx. cement thru drill pipe.  
Spotted 10 sx. cement in rathole.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor White & Ellis Drilling, Inc.  
401 E. Douglas, Suite 500, Wichita, Ks. 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.  
Ernest Sifford (employee of owner) or (owner or operator) of the  
above-described well, being first duly sworn on oath, says: That I have knowledge of the  
facts, statements, and matters herein contained and the log of the above-described well as  
filed and that the same are true and correct. So help me God.

(Signature) Ernest Sifford  
401 E. Douglas #500 Wichita  
(Address) Kansas 67202


SUBSCRIBED AND SWORN TO before me this 29<sup>th</sup> day of September 1983

DAVID F. JAMIS  
NOTARY PUBLIC  
STATE OF KANSAS  
My Appt. Exp. 6-10-87

David F. Jamis RECEIVED  
Notary Public STATE CORPORATION COMMISSION

My Commission expires:

OCT 3 1983  
10-3-83  
CONSERVATION DIVISION  
Wichita, Kansas



WHITE

AND ELLIS DRILLING, Inc.

DRILLERS LOG

OPERATOR: Landmark Oil Exploration 105 S. Broadway, Suite 730, Wichita, Ks. 67114

CONTRACTOR: White & Ellis Drilling, Inc., 401 E. Douglas, Suite 500,  
Wichita, Ks. 67202

Lease Name Byer Well No. #1

Sec. 17 T. 24S R. 12W Spot 100' W of C W/2 NE SE

County Stafford State Kansas Elevation \_\_\_\_\_

Casing Record:

Surface: 8 5/8" @ 324' with 185 sx. 2%gel  
3%cc

Production: \_\_\_\_\_ @ \_\_\_\_\_ with \_\_\_\_\_ sx.

Type Well: D & A Total Depth 3925'

Drilling Commenced 9-6-83 Drilling Completed 9-11-83

Formation	From	To	Tops
Cellar	0	7	Anhydrite 720
Shale, Lime	7	2280	
Lime, Shale	2280	2635	
Shale, Lime	2635	3925	

RECEIVED  
STATE CORPORATION COMMISSION

OCT 3 1983

CONSERVATION DIVISION  
Wichita, Kansas