

29

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely.  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas 67202

WELL PLUGGING RECORD

Stafford County, Sec. 21 Twp. 24 Rge. 12 (E) (W) x  
Location as "NE/CNWxSWx" or footage from lines SE SE NE

Lease Owner Graves Drilling Co.  
Lease Name Byer Well No. #1  
Office Address 505 Union Center Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole)  
Date well completed 19  
Application for plugging filed 5-28-71 19  
Application for plugging approved 19  
Plugging commenced 6-8-71 19  
Plugging completed 6-10-71 19  
Reason for abandonment of well or producing formation



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced?

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein  
Producing formation Depth to top Bottom Total Depth of Well 4104' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"	4104'	3119.61'
				8 5/8"	270'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Made bottom hole plug back with sand to 3500'. Mix and dumped 5 sacks cement thru dump bailer.  
Squeezed hole with 2 sacks hulls, 15 sacks gel and 100 sacks cement.


RECEIVED  
STATE CORPORATION COMMISSION  
JUN 14 1971 6-14-71  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Southwest Casing Pulling Co.  
Address Box 364, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
Southwest Casing Pulling Co. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. C. Spencer Sec  
Box 364 Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 11 day of June, 1971



Sydney D. Will  
Notary Public.

My commission expires October 1972

FORMATION TOPS:

	<u>Electric Log Measurements</u>
8-5/8" Surface Casing	270
Anhydrite	702 (+1182)
B/ Anhydrite	722 (+1162)
Heebner	3323 (-1439)
Toronto	3338 (-1454)
Douglas Shale	3358 (-1474)
Brown Line	3481 (-1597)
Lansing-Kansas City	3507 (-1623)
B/ Kansas City	3768 (-1884)
Marmaton	3799 (-1915)
Kinderhook Shale	3829 (-1945)
Viola	3912 (-2028)
Simpson Shale	4045 (-2161)
Simpson Sand	4062 (-2178)
Arbuckle	4101 (-2217)
Total Depth	4104 (-2220)

STRUCTURAL POSITION:

The structural position of this test can be compared with the following tests:

	SHAWVER-ARMOUR #1 GRIEVE NE NE SE <u>21-24S-12W</u>	STICKLE #1 BYER SE SE NE <u>21-24S-12W</u>	REX & MORRIS #1 REID SW SW NW <u>22-24S-12W</u>
Heebner	-1434	-1439	-1438
Brown Line	-1592	-1597	-1596
Lansing-Kansas City	-1617	-1623	-1623
Base Kansas City	-1879	-1884	-1884
Kinderhook Shale	-1939	-1945	-1944
Viola	-2020	-2028	-2023
Simpson Shale	-	-2161	-
Simpson Sand	-	-2178	-
Arbuckle	-	-2217	-
Total Depth	-2022	-2220	-2074