

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittig Building  
Wichita, Kansas

Stafford

County. Sec. 21 Twp. 24S Rge. 12 (NW) (W)

Location as "NE/CNW%SW%" or footage from lines SW SE NW

Lease Owner Stearns Petroleum, Inc.

Lease Name Piepmeier Well No. 2

Office Address Box 313, Russell, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry

Date well completed September 29 19 56

Application for plugging filed September 29 19 56

Application for plugging approved September 29 19 56

Plugging commenced September 29 19 56

Plugging completed September 29 19 56

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well R. M. Brundage

Producing formation Depth to top Bottom Total Depth of Well 4151' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole filled with heavy mud to 240 feet  
1/3 Sacks Hulls  
Halliburton Plug at 240 feet  
20 Sacks cement through drill pipe  
Filled with mud to 35 feet  
1/3 sacks Hulls  
Halliburton Plug  
10 sacks cement - Hole plugged at 3:00 p.m. 9-29-56

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Stearns Petroleum, Inc.

Address Box 313, Russell, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.

D. D. Stewart (employee of owner) or ( ) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. D. D. Stewart,

(Signature) *D. D. Stewart*

(Address)

SUBSCRIBED AND SWORN to before me this 1st day of October, 19 56

My commission expires April 5, 1958

*Betty Lou Miller*  
Betty Lou Miller Notary Public

STATE OF KANSAS

PLUGGING  
FILE SEC 21 T. 24 R. 12W  
BOOK PAGE 104 LINE 5

OCT 2 1956  
10-2-56  
CONSERVATION DIVISION

Operator: Stearns Petroleum, Inc.  
 Contractor: Stearns Petroleum, Inc.  
 Commencement Date: September 13, 1956  
 Completion Date: September 29, 1956  
 Elevation: 1894' K. B.  
 I. P.: Dry

Location  
 SW SE NW  
 Section 21-24S-12W  
 Stafford County, Kansas

Surface Casing: Ran 13 joints of 8-5/8" casing set at 252' cemented with 225 sacks Pozmix and 2% Calcium Chloride. Plug down at 5:15 P. M., September 14, 1956

WELL LOG

Clay	0	35
Sand & Shale	35	130
Shale & Shells	130	200
Red Bed	200	252
Red Rock & Red Bed	252	420
Sand and Red Bed	420	717
Anhydrite	717	735
Shale	735	785
Shale & Shells	785	1680
Lime & Shale	1680	3526
Lime	3526	3793
Lime & Shale	3793	3845
Lime	3845	3880
Lime & Shale	3880	3948
Cherty Lime	3948	4017
Chert	4017	4020
Shale	4020	4075
Shale & Lime	4075	4151
R.T.D.	4151	
Tops:		
Heebner	3347	(-1453)
Toronto	3364	(-1470)
Douglas	3382	(-1488)
Brown Lime	3501	(-1607)
Lansing-Kansas City	3528	(-1634)
Base Kansas City	3847	(-1953)
Viola	3932	(-2038)
Simpson	4054	(-2160)
Arbuckle	4118	(-2224)
R. T. D.	4154	(-2260)

STATE OF KANSAS )  
 ) SS:  
 COUNTY OF RUSSELL )

I hereby certify that the above information is true and correct to the best of my knowledge.

STEARNS PETROLEUM, INC.

BY: *O. G. Stearns*  
 O. G. Stearns, President

SUBSCRIBED AND SWORN TO BEFORE ME, A Notary Public, this 1st day of October, 1956.

My Commission Expires: April 5, 1958

*Betty Lou Millee*  
 Betty Lou Millee, Notary Public

RECEIVED  
 NOTARY COMMISSION

PLUGGING
FILE SEC. <u>21</u> T. <u>24</u> R. <u>12W</u>
BOOK PAGE <u>104</u> LINE <u>5</u>