

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

WELL PLUGGING RECORD

Stafford County. Sec. 21 Twp. 24S Rge. 21 (E) (W)

Location as "NE/CNW\*SW\*" or footage from lines SE/4 NE/4 SE/4

Lease Owner Walters Drilling Co., Inc.

Lease Name Grieve Well No. 1

Office Address 510 Orpheum Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed June 19, 19 53

Application for plugging filed July 15, 19 53

Application for plugging approved July 15, 19 53

Plugging commenced July 26, 19 53

Plugging completed July 26, 19 53

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production None 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives, Pratt, Kansas

Producing formation Viola Depth to top 3910' Bottom 3916' Total Depth of Well 4127 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Viola	Water & Oil	3910'	3916'	8 5/8" 5 1/2"	289' 4117'	None 3206'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Baker plug set at 3950'. Perf. squeezed w/250 sx cement. Cement drilled out to 3918'. Top Perf. 3906'. P. B. 3918' to 3895', sand. 3895' to 3860' cement 5 sx. Squeezed with 15 sx magcogel and plugged with 80 sx. cement.

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Sun Oilwell Cementing Co.  
Address Box 89, Hays, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK, ss.  
ROBERT F. WALTERS (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Robert F. Walters  
510 Orpheum Building, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 30th day of July, 19 53.

STATE CORPORATION COMMISSION  
Notary Public.

My commission expires March 10, 1956.

PLUGGING  
FILE SEC 21 T 24 R 12W  
BOOK PAGE 115 LINE 9

24-7369-S 3-53-20M

JUL 31 1953

GRIEVE NO. 1

Location: SE NE SE Sec. 21-24S-12W Stafford County, Kansas Date Spudded: 6-3-53  
Operator: Walters Drilling Co., Inc. Rotary Completion: 6-19-53  
Contractor: Walters Drilling Co., Inc. Elevation: 1876 Gr  
Surface Casing: 8 5/8" set at 288 ft. with 225 sacks cement and 3 sacks Cal. Chloride 1879 DF  
Oil String: 5 1/2" set at 4117 ft. with 75 sacks cement 1881 KB

L O G

(Figures indicate bottom of formation)

Surface	0 to 288
Shale and shells	687
Anhydrite	708
Shale and Shells	1655
Shale and Lime	1780
Shale and shells	1867
Shale and Lime	3627
Lime	3770
Lime and Shale	3918
Cherty Lime	4041
Sandy Shale	4056
Shale and Lime	4127
Total Depth (Rotary)	4127

The undersigned, Robert F. Walters, hereby certifies that the above log is a true and correct log of the formations encountered in drilling the above noted well as reflected by the Daily Drilling Reports.

WALTERS DRILLING CO., INC.

By Robert F. Walters

Subscribed and sworn to before me  
this 23rd day of June, 1953.

Pauline Hudson  
Notary Public

My commission expires: March 10, 1956

