


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Stafford County. Sec. 10 Twp. 24 Rge. 12 (E) (W)
Location as "NE/CNW/SW" or footage from lines NE/ SE/ SW/
Lease Owner Morgenstern & Spector
Lease Name Byer Well No. 3
Office Address Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed 9-19-47 _____ 19____
Application for plugging filed Oct. 18, 1960 _____ 19____
Application for plugging approved Oct. 19, 1960 _____ 19____
Plugging commenced October 24 1960 _____ 19____
Plugging completed October 26 1960 _____ 19____
Reason for abandonment of well or producing formation Failure to produce
profitably
If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot. St John. Ks
Producing formation Viola Depth to top 3837 Bottom 3857 Total Depth of Well 3857 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	648'	none
				5 1/2	3837'	2693'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged back with sand to 3825 feet. Dumped 5 sacks Cement.
Mudded hole up to 300 feet. Set a Ten foot Rock Bridge.
Dumped 20 sacks Cement. Mudded hole to 40 feet. Set a Rock-
Bridge. And dumped 10 sacks Cement.

NOV 21 1960
11-21-60
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor LYNCH CASING PULLING COMPANY. NO. 457
Address R. Rt. 4 GREAT BEND. KANSAS

STATE OF Kansas, COUNTY OF Russell, ss.
Morgenstern & Spector, Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Handwritten Signature]

(Address) _____

SUBSCRIBED AND SWORN TO before me this 1st day of November, 1960

My commission expires Dec 1, 1964
Elsie Lady
Notary Public.



COPY


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

Company - CITIES SERVICE OIL COMPANY
Farm - Byor No. 3

SEC. 10 T. 24 R12W
NE SE SE
990' N & 330' W of SE corner

Total Depth. 3857' SLM
Comm. 9-9-47 Comp. 9-19-47
Shot or Treated. Acid w/500 gals.
Contractor. R. W. Rino Drilling Co.
Issued. 11-22-47

County. Stafford
KANSAS



CASING:

8-5/8" 648' Com. w/350 sx
5-1/2" 3837' Com. w/200 sx

Elevation. _____

Production. Phy. Pot: 130 BO &
35 BW, 24 hours.

Figures indicate Bottom of Formations.

surface soil & sand	0-40
sand & shale	190
rod rock & shale	640
anhydrite	650
shale & shells	1220
salt & shale	1510
shale & shells	1835
shale w salt	2024
lime w shale	2360
shale	2755
shale & shells	2840
shale	3025
lime	3280
lime brkn	3460
lime	3782
shale	3837
lime	3841
cored lime (roc. 8")	3842
cored lime & chert (roc. 4")	3844
lime & chert RTD	3857 SLM
Total Depth	

RECEIVED
STATE CORPORATION COMMISSION
OCT 19 1960
CONSERVATION DIVISION
Wichita, Kansas

Tops:

Lansing	3452
Kinderhook	3751
Viola	3837
Penetration	20

Loaded hole w/1000' water.

Drilled shoe and cleaned out to
bottom; good show oil.