



WELL RECORD

Company Cities Service Oil Co. Well No. 2 Farm Dyer  
 Location 330' N. and 660' E. of S/4 Corner Sec. 10 T. 24 R. 12W  
 Elevation 1878 County Stafford State Kansas  
 Drlg. Comm. July 14, 1942 Contractor Earl F. Wakefield  
 Drlg. Comp. August 2, 1942 Acid None  
 T. D. 3871' Initial Prod. Dry - Plugged and Abandoned

CAGING RECORD:

8-5/8" @ 398' cem. 250 px cement.

FORMATION RECORD:

surface clay	0-35
sand	150
shale red	398
red bed	665
anhydrite	677
shale & shells	1155
salt & shale	1410
shale & shells	1516
lime	1915
lime sandy	1960
lime	1976
sand	2015
lime	2180
lime broken	2347
lime sandy	2393
lime	2398
lime broken	2515
lime sandy	2546
lime broken	2810
lime	2846
shale	2885
lime	2936
shale & shells	2996
shale	3000
lime	3055
shale	3067
lime	3116
lime soft	3161
lime	3167
shale & shells	3189
lime	3290
shale	3305
lime & shale	3346
shale	3464
lime	3559
lime soft	3571
lime	3587
lime hard	3603
lime broken	3659

lime	3672
lime soft	3681
lime	3768
lime & shale	3772
lime	3790
shale	3849
lime	3851
lime cored (rec. 2')	3855
lime & dolomite	3863
lime & chert	3871 T. D.

Top Viola	3849'
Penetration	22'
Total Depth	3871'

Aug. 1, 1942 - Halliburton drill stem test, packer at 3849, T. D. 3855, open 30 mins., made 30' rotary mud, no oil.

Slope Test:	900'	10
	1400'	0
	2100'	3/49
	2600'	10
	3250'	8

**PLUGGING**  
 FILE SEC 10 T24 R12W  
 BOOK 46 LINE 18

