

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-001-02927-00-00
Spot: NWNEENW Sec/Twnshp/Rge: 4-25S-20E
5250 feet from S Section Line, 3120 feet from E Section Line
Lease Name: STEPHENS Well #: 1
County: ALLEN Total Vertical Depth: 850 feet

Operator License No.: 8228
Op Name: STEPHENS, WESLEY WILLIAM AND/O
Address: 1105 3400TH ST
MORAN, KS 66755

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	850		10 SX
SURF	8.625	20		5 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/23/2015 12:00 AM
Plug Co. License No.: 33977 Plug Co. Name: E K ENERGY LLC
Proposal Rcvd. from: DAVID KIMZEY Company: _____ Phone: (620) 496-6257

Proposed Plugging Method: RUN 1" PIPE TO TD PUMP 30 SX, PULL PIPE TO 500' PUMP 30 SX, PULL PIPE TO 250' FILL TO SURFACE. RUN DOWN BACK SIDE TO 250' FILL TO SURFACE.

Plugging Proposal Received By: _____ Witness Type: PARTIAL
Date/Time Plugging Completed: 11/23/2015 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report: _____ Perfs: _____
Ran down the 4.5" casing and shot the well at 500' and 250'. Ran 1" pipe down the inside of the 4.5" casing to TD. Pumped 30 sacks of cement through the 1" pipe at TD. Pulled 1" pipe up to 500'. Pumped 30 sacks of cement through the 1" pipe at 500'. Pulled 1" pipe up to 250'. Pumped and circulated cement from 250' to surface. Pulled the 1" pipe out of the well and topped the well off with cement. A total of 120 sacks of portland cement was reported used to plug this well.

RECEIVED
KCC DIST # 3
JAN 06 2016
CHANUTE, KS

RD

Remarks: _____
Plugged through: TBG

District: 03 Signed _____ (TECHNICIAN)

KCC WICHITA
JAN 11 2016
RECEIVED

Form CP-2/3
220
1-15-2016