

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-003-19002-00-00
Spot: SENWSWNW Sec/Twnshp/Rge: 26-22S-19E
3343 feet from S Section Line, 4651 feet from E Section Line
Lease Name: BURKE Well #: W 2 A
County: ANDERSON Total Vertical Depth: 858 feet

Operator License No.: 33097
Op Name: SOUTHERN STAR CENTRAL GAS PIPE
Address: 4700 HWY 56
OWENSBORO, KY 42301

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.375	768	768	
SURF		7		

Well Type: EOR UIC Docket No: E26730.3 Date/Time to Plug: 10/16/2015 12:00 AM
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.
Proposal Rcvd. from: STERLING BARKER Company: Phone: (785) 448-4816

Proposed Plugging Method: Run workstring to bottom, and pump cement to surface. Pull workstring out and top off with cement. Tie onto 2' and squeeze cement until desired amount of pressure is achieved. Cut well off 3' below surface.

Plugging Proposal Received By: LEVI SHORT WitnessType: NONE
Date/Time Plugging Completed: 10/19/2015 12:00 AM KCC Agent: LEVI SHORT

Actual Plugging Report:

WASH DOWN TO 823 FEET. RUN 1-INCH TUBING TO TD AND PUMP TO SURFACE WITH PORTLAND CEMENT. WASH DOWN OUTSIDE CASING TO 270 FEET, THEN PUMP CEMENT TO SURFACE. A TOTAL OF 205 SACKS OF CEMENT WERE USED TO PLUG WELL.

Perfs:

Top	Bot	Thru	Comments
816	822		
RECEIVED KCC DIST # 3 DEC 30 2015 CHANUTE, KS LS			

Remarks:

Plugged through: TBG

District: 03

Signed 

(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

JAN 06 2016

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

CC UIC
1-15-2016
720