

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-003-02550-00-00
Spot: SENWNW Sec/Twnshp/Rge: 26-22S-19E
4247 feet from S Section Line, 4249 feet from E Section Line
Lease Name: BURKE Well #: 12
County: ANDERSON Total Vertical Depth: 405 feet

Operator License No.: 33097
Op Name: SOUTHERN STAR CENTRAL GAS PIPE
Address: 4700 HWY 56
OWENSBORO, KY 42301

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4	0		0 SX
PROD	2	404	404	
SURF	8	0		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/13/2015 12:00 AM
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.
Proposal Rcvd. from: STERLING BARKER Company: _____ Phone: (785) 448-4816

Proposed Plugging Method: PULL ROD AND TUBING AND 2.375" OUT OF 4". RUN BOND LOG ON 4" TO DETERMINE IF GOOD CEMENT ON OUTSIDE OF 4". PERFORATE IF NEEDED. RUN WORKSTRING INSIDE 4" AND PUMP CEMENT TO SURFACE. PULL WORKSTRING OUT AND TOP OFF WITH CEMENT. TIE ONTO 4" AND SQUEEZE CEMENT UNTIL DESIRED PRESSURE IS ACHIEVED OR WHEN GOOD CEMENT REACHES SURFACE ON OUTSIDE OF 4" IF PERFORATING WAS NECESSARY. CUT WELL OFF 3' BELOW SURFACE.

Plugging Proposal Received By: LEVI SHORT Witness Type: NONE
Date/Time Plugging Completed: 10/14/2015 12:00 AM KCC Agent: LEVI SHORT

Actual Plugging Report:

WASH DOWN TO 405 FEET. RUN 1-INCH TUBING TO TD AND PUMP TO SURFACE WITH PORTLAND CEMENT. A TOTAL OF 105 SACKS OF CEMENT WERE USED TO PLUG WELL.

Perfs:


RECEIVED
KCC DIST # 3
DEC 30 2015
CHANUTE, KS

LS

Remarks:

Plugged through: TBG

District: 03

Signed 

(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

JAN 06 2016

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

220
1-15-2016