

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-003-20298-00-00  
Spot: SWSNWNW Sec/Twnshp/Rge: 26-22S-19E  
3984 feet from S Section Line, 4329 feet from E Section Line  
Lease Name: BURKE Well #: O-3  
County: ANDERSON Total Vertical Depth: 865 feet

Operator License No.: 33097  
Op Name: SOUTHERN STAR CENTRAL GAS PIPE  
Address: 4700 HWY 56  
OWENSBORO, KY 42301

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|------|------------|-------------|---------|
| PROD   | 2    | 0          |             | 0 SX    |
| SURF   | 6.25 | 0          |             | 0 SX    |

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/14/2015 12:00 AM  
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.  
Proposal Rcvd. from: STERLING BARKER Company: \_\_\_\_\_ Phone: (785) 448-4816

Proposed Plugging Method: Run workstring to bottom, and pump cement to surface. Pull workstring out and top off with cement. Tie onto 2' and squeeze cement until desired amount of pressure is achieved. Cut well off 3' below surface.

Plugging Proposal Received By: LEVI SHORT WitnessType: NONE  
Date/Time Plugging Completed: 10/14/2015 12:00 AM KCC Agent: LEVI SHORT

Actual Plugging Report:

WASH DOWN TO 620 FEET. RUN 1-INCH TUBING TO TD AND PUMP TO SURFACE WITH PORTLAND CEMENT. HOOK ON TO CASING AND SHUT IN AT 500 PSI. A TOTAL OF 20 SACKS OF CEMENT WERE USED TO PLUG WELL.

Perfs:

RECEIVED  
KCC DIST #3  
DEC 30 2015  
CHANUTE, KS

LS

Remarks:

Plugged through: TBG

District: 03

Signed 

(TECHNICIAN)

Received  
KANSAS CORPORATION COMMISSION

JAN 06 2016

CONSERVATION DIVISION  
WICHITA, KS

Form CP-2/3

no  
1-15-2016