

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-003-21749-00-00
Spot: SWNWSWNW Sec/Twnshp/Rge: 26-22S-19E
3332 feet from S Section Line, 4958 feet from E Section Line
Lease Name: BURKE Well #: O-11
County: ANDERSON Total Vertical Depth: 850 feet

Operator License No.: 33097
Op Name: SOUTHERN STAR CENTRAL GAS PIPE
Address: 4700 HWY 56
OWENSBORO, KY 42301

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2	0		0 SX
SURF	6.25	0		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/16/2015 12:00 AM
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.
Proposal Rcvd. from: STERLING-BARKER Company: _____ Phone: (785) 448-4816

Proposed Plugging Method: Run workstring to bottom, and pump cement to surface. Pull workstring out and top off with cement. Tie onto 2' and squeeze cement until desired amount of pressure is achieved. Cut well off 3' below surface.

Plugging Proposal Received By: LEVI SHORT Witness Type: NONE
Date/Time Plugging Completed: 10/16/2015 12:00 AM KCC Agent: LEVI SHORT

Actual Plugging Report:

WASH DOWN TO 848 FEET. RUN 1-INCH TUBING TO TD AND PUMP TO SURFACE WITH PORTLAND CEMENT. HOOK ON TO CASING AND SHUT IN AT 450 PSI. A TOTAL OF 32 SACKS OF CEMENT WERE USED TO PLUG WELL.

Perfs: _____

RECEIVED
KCC DIST # 3
DEC 30 2015
CHANUTE, KS

LS

Remarks:

Plugged through: TBG

District: 03

Signed _____

(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

JAN 06 2016

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

no
1-15-2016