

STATE OF KANSAS
STATE CORPORATION COMMISSION


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Stafford County. Sec. 7 Twp. 24S Rge. 13W (E) (W)

Location as "NE/CNW/SW" or footage from lines NE SW NE
Lease Owner The Texas Company
Lease Name Blanche Henderson Well No. 2
Office Address 614 Bitting Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed May 23 19 56
Application for plugging filed March 14 19 57
Application for plugging approved March 15 19 57
Plugging commenced April 2 19 57
Plugging completed April 3 19 57
Reason for abandonment of well or producing formation

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. R. M. Brundage
Producing formation Depth to top Bottom Total Depth of Well 3963 Feet
Show depth and thickness of all water, oil and gas formations. PBD 3713

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10-3/4"	819'	None
				7"	3990'	1930'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

3713' to 3690' - Sand
3690' to 3660' - 6 Sacks Cement
3660' to 270' - Heavy Mud
370' to 260' - Rock Bridge
260' to 210' - 25 Sacks Cement
210' to 10' - Heavy Mud
10' to Bottom of Cellar - 10 Sacks Cement

RECEIVED

FEB 15 1958
2-15-58
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor R & S Pipe Pulling Company
Address Box 192, Ellinwood, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
M. C. Harrell (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) M. C. Harrell
614 Bitting Bldg., Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 14th day of February, 19 58
Howard Kistler Notary Public.

My commission expires Sept. 20, 1960

PLUGGING
SEC 7, T24R13W
50M PAGE 148 LINE 5

LOG OF WELL

FORM PO-214 SHEET 1 (4-54) 1551

BLANCHE HENDERSON NO. 2

SHEET **1**

OWNER The Texas Company DIVISION Oklahoma DATE MADE July 11, 1956
 DISTRICT Kansas LEASE Blanche Henderson WELL NO. 2
 STATE Kansas COUNTY OR PARISH Stafford TWP. 218 RANGE 13N SEC. 7
 LOCATION OF WELL NE SW NE

COMMENCED RIGGING UP 4-19-56 COMMENCED DRILLING 4-19-56 COMPLETED DRILLING 5-23-56
 DAY DRILLER _____ NIGHT DRILLER _____ CONTRACTOR Stickle Drlg. Co.

CABLE FROM _____ TO _____ ROTARY FROM 0' TO 3963' COMPANY RIG NO. _____
 TOTAL DEPTH 3963' MEASURED BY M. C. Harrell ELEVATION KB - 1923
WD 3713' UL - 1920
UL - 1917

CASING RECORD

SIZE	WEIGHT	PUT IN WELL		PULLED OUT		LOST IN WELL		SHOES		PACKERS			
		FEET	INS.	FEET	INS.	FEET	INS.	LENGTH	MARK	KIND	LENGTH	SET AT	
<u>10-3/4"</u>	<u>32.75#</u>	<u>819</u>											<u>FT.</u>
<u>7"</u>	<u>20#</u>	<u>3990.</u>											<u>FT.</u>
													<u>FT.</u>
													<u>FT.</u>
													<u>FT.</u>
													<u>FT.</u>
<u>10-3/4" casing set at 811' with 550 sacks cement, 1/4# floccule per sack, 14 cu. Cement cemented.</u>													<u>FT.</u>
<u>7" casing set at 3062' with 150 sacks cement, 3/4# flocc.</u>													<u>FT.</u>

WAS CASING CEMENTED? _____ IF SO, HOW MANY BAGS OF CEMENT USED? _____
 LINER: STATE SIZE AND WEIGHT _____ WHERE SET _____ FT. AND INS. BLANK _____ FT. AND INS. PERFORATED _____
 HOW PUT TOGETHER _____ COUPLING _____ FLUSH-JOINT _____ INSERTED _____
 REMARKS: _____

EQUIPMENT RECORD

TUBING				SUCKER RODS			PUMPING OUTFIT
SIZE	WEIGHT	FEET	INS.	FEET	INS.	SIZE AND KIND	DESCRIPTION, KIND, SIZE, ETC.

FLOWING, PUMPING, GASSEY OR DRY Dry PRODUCTION FIRST 24 HOURS _____ PRODUCTION SETTLED _____
 IF GAS WELL, OPEN FLOW CAPACITY _____ SHUT IN PRESSURE _____ ROCK PRESSURE _____
 KIND OF SHOT _____ SIZE OF SHOT, QUARTS _____
 NUMBER OF SHELLS _____ SIZE OF SHELLS _____ INCHES, DIAMETER _____
 LENGTH OF SHELLS _____ FEET _____ INCHES _____ TOP OF SHOT _____
 BOTTOM OF SHOT _____ ANCHOR _____ WELL BRIDGED TO _____
 TOTAL DEPTH OF WELL _____ NUMBER OF SHOT _____ PRODUCTION BEFORE SHOT _____ BBL. PER DAY _____
 PRODUCTION AFTER SHOT _____ BBL. PER DAY. SHOT FURNISHED BY _____
 NAME OF SHOOTER _____ SHOT INSPECTED _____ BY _____ (COMPANY EMPLOYEE)
 COMMENCED DRILLING DEEPER _____ COMPLETED _____ DRILLING DEEPER _____
 TOTAL DEPTH _____ PRODUCTION FIRST 24 HOURS _____ PRODUCTION SETTLED _____

REMARKS:
PLUGGING
 FILE SEC 7-T-24R-134
 BOOK PAGE 148 LINE 5

Blanche Henderson #2
Kattlesnake East Pool
TB 3963' - WD 3713'
Completed Drilling 5-23-56

NOTE: IF WELL WAS DRY, STATE UNDER REMARKS, WHEN, HOW, AND BY WHOM PLUGGED.
 STATE UNDER REMARKS ANYTHING OF INTEREST NOT COVERED IN LOG.
 IF THE SPACE PROVIDED FOR REMARKS IS NOT SUFFICIENT WRITE ON BOTTOM OF LAST SHEET OF LOG.

TOTAL NUMBER OF SHEETS _____

Handwritten note: 13-25-56 in 800cc, 350cc (w/acid)

The Texas Company
Tulsa, Oklahoma

Tulsa, Oklahoma
May 7, 1956

CONTRACTOR: Stickle Drilling Company
Drilling Commenced: April 19, 1956
Drilling Completed: May 3, 1956

Blanche Henderson #2 -
NE SW NE - Sec. 7-24S-13W,
Stafford County, Kansas.


Drillers Log

DEPTH FIGURES INDICATES BASE OF FORMATION

Sand	130
Shale & Shells	230
Red Bed Shale & Shells	445
Red Bed & Shells	585
Shale & Shells	812
Anhydrite	845
Shale	1000
Salt, Shale & Shells	1460
Shale & Shells	1795
Lime & Shale	2045
Shale & Lime	2245
Lime & Shale	2325
Sandy Lime & Shale	2405
Shale & Shells	2635
Lime & Shale	3025
Shale & Lime	3135
Lime	3250
Lime & Shale	3316
Lime	3450
Shale & Lime	3580
Lime	3647
Lime & Shale	3690
Lime	3800
Lime & Shale	3845
Lime	3890
Lime & Dolomite	3920
Lime & Shale	3923
Conglomerate	3945
Shale & Lime	3963 TD

I, Fred E. Stickle, hereby certify the above to be a true and complete Drillers Log of The Texas Company's Blanche Henderson #2 * NE SW NE - Section 7-24S-13W, Stafford County, Kansas.


Fred E. Stickle


Lillian T. Bonham
Notary Public

February 13, 1960
My Commission Expires