

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

STAFFORD County. Sec. 6 Twp. 24 Rge. 13 ~~W~~ W (W)

Location as "NE/CNW/SW" or footage from lines NE NE NE

Lease Owner PETROLEUM, INC.

Lease Name HUNT Well No. 1

Office Address Route 2, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed August 4, 19 49

Application for plugging filed August 2, 19 57

Application for plugging approved August 8, 19 57

Plugging commenced September 9, 19 57

Plugging completed September 13, 19 57

Reason for abandonment of well or producing formation

Depletion of producible zones

If a producing well is abandoned, date of last production February 11, 19 57

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well R.M. Brundege Hoisington, Kansas

Producing formation Kansas City Depth to top 3551' Bottom --- Total Depth of Well 3681 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Kansas City	Water and little oil	3675'	3681'	8-5/8" 5-1/2"	325' 3675'	None 3100'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with crushed rock from 3681' to 3665' and placed 5 sacks cement on top of rock. Globe Oil Well Cementation Co. pumped 25 sacks Davis Gel (mud) on top of cement followed by a plug. Filled hole to base of well cellar with 80 sacks cement, 2 sacks calcium chloride.

RECEIVED
STATE CORPORATION COMMISSION
9-18-57
SEP 18 1957
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Morgan Well Plugging Service
Address 102 West 18th Street, Hutchinson, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
Don Searle (employee of owner) or (owner/operator)

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Don Searle
Route 2, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 14th day of September 19 57

Notary Public. [Signature]

My commission expires July 11, 1960

PLUGGING
FILE SEC. 6 T. 24 R. 13 W.
BOOK PAGE 33 LINE 13

LEASE: Hunt Well No. 1
OWNER: Petroleum, Inc., Wichita, Kansas

LOCATION: NE NE NE/4, Sec. 6-24S-13W
Stafford County, Kansas

CONTRACTOR: J. A. Melland, Hutchinson, Kansas

Commenced Drilling: July 15, 1949
Finished Drilling: July 26, 1949

FORMATION	FROM	TO
Cellar	0	5
Shale	5	40
Sand	40	150
Shale and shells	150	285
Sand	285	310
Shale	310	325
		Set and cemented 8-5/8" steel casing at 325' with 300 sacks of cement. Finished at 5:15 PM, 7/16/49.
Red bed	325	520
Sand	520	550
Red bed	550	645
Shale and shells	645	795
Anhydrite	795	815
Shale and shells	815	1210
Shale and shells	1210	1490
Salt	1490	1560
Salt and shale	1560	1600
Shale and shells	1600	1680
Lime and shale	1680	1890
Lime	1890	1925
Lime and shale	1925	2325
Shale and shells	2325	2505
Shale and lime	2505	2700
Shale and shells	2700	2850
Lime and shale	2850	3135
Lime	3135	3400
Lime and shale	3400	3535
Lime	3535	3560
Lime and shale	3560	3633
Lime	3633	3685

Ran Drill Stem test at 3685'

Rotary Total Depth 3685' Set and cemented 5"OD, 13.30# National Steel Casing at 3675' with 75 sacks of cement - Finished at 7:15 PM, 7/26/49.

Slope tests were taken at 500' intervals to total depth and no deflections from vertical were recorded.

J. A. Melland

PLUGGING
FILE SEC. 6 T. 24 R. 13W
BOOK PAGE 33 LINE 13

RECEIVED
STATE COMMISSION COMMISSIONERS
SEP 13 1949
CONSOLIDATION DIVISION
Wichita, Kansas