

WELL PLUGGING RECORD

OR

FORMATION PLUGGING RECORD

Strike out upper line when reporting plugging of formations.

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Stafford County. Sec. 3 Twp. 24 Rge. 13 ~~XXXXXX(W)~~

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NW corner of N $\frac{1}{2}$ NW $\frac{1}{4}$

Lease Owner Crown Oil Company

Lease Name Gillmore Well No. 1

Office Address Box 164, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed April 20, 1950

Application for plugging filed April 20 1950

Application for plugging approved April 20 1950

Plugging commenced April 20 1950

Plugging completed April 20 1950

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

NORTH

x			

Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well C. D. Stough

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

4000' to 315' filled with heavy rotary mud, and one plug set with fifteen sacks of cement, then filled to 40' with heavy rotary mud; then filled with one plug and ten sacks of cement to top of hole.

Rec'd
RECEIVED
Conservation
5-10-50
MAY 10 1950
STATE CORPORATION
COMMISSION
KANSAS

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Crown Oil Company
Address Box 164, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.

H. R. Buick, Drilling Superintendent (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. HILTON DRILLING COMPANY, INC.

(Signature) By: H. R. Buick
Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 5th day of May, 1950.

My commission expires June 13, 1951 Henry Peacock Notary Public.

22-2625 2-48-15M
PLUGGING
FILE SEC-3 Twp R13W
BOOK PAGE 2 LINE 21

DRILLER'S LOG

COMPANY: CROWN OIL COMPANY, INC. LOCATION: NW Corner of the N $\frac{1}{2}$ NW $\frac{1}{4}$
 Section 3-24S-13W
 CONTRACTOR: HILTON DRILLING COMPANY, INC. Stafford County, Kansas
 FARM NAME: GILLMORE #1 ELEVATION: 1903 D.F.
 COMMENCED: April 4, 1950 CASING USED: 8-5/8" at 315 feet with 225 sacks
 COMPLETED: April 20, 1950

Cellar	4	Lime	3637
Surface Sand	134	Lime	3681
Sand and Shale	154	Lime	3682
Shale	195	Lime	3705
Red Bed	220	Lime	3729
Sand	260	Lime	3770
Red Bed	312	Lime	3807
Red Bed and Shale	640	Lime	3840
Red Bed and Shale	760	Chert	3875
Anhydrite	785	Lime and Chert	3900
Shale and Shells	950	Shale and Lime	3940
Shale and Shells	1180	Lime	3949
Salt, Shale and Shells	1415	Lime	3977
Shale and Shells	1625	Lime	4000
Broken Lime	1650		
Lime and Shale	1765	<u>Total Depth</u>	<u>4000</u>
Lime	1860		
Broken Lime	1970		
Broken Lime and Shale	2110		
Lime and Shale	2205		
Lime	2275	<u>GEOLOGICAL TOPS</u>	
Lime and Shale	2353	Heebner Shale	3339
Lime and Shale	2465	Lansing (white)	3520
Broken Lime and Shale	2575	Viola	3831
Shale and Lime Shells	2710	Simpson	3885
Shale and Lime	2795	Arbuckle	3939
Shale, Lime and Shells	2905		
Shale and Shells	3025		
Shale and Lime	3075		
Broken Lime	3110		
Lime	3210		
Lime	3230		
Lime	3287		
Lime	3350		
Lime	3374		
Shale and Shells	3410		
Shale	3480		
Lime	3525		
Lime	3565		
Lime	3605		

RECEIVED
 MAY 10 1950
 STATE REGISTRATION
 COMMISSION
 KANSAS

STATE OF KANSAS)
) SS
 COUNTY OF BARTON)

I, the undersigned, being duly sworn on oath, state that the above statement and log are true and correct record and log of the well drilled at the location above described.

HILTON DRILLING COMPANY, INC.
 By H. R. Busch

Subscribed and sworn before me this 14th day of May, 1950.

PLUGGING
 FILE SEC. 3-24-13W
 NOTARY PUBLIC

Henry Peacock
 Notary Public

My commission expires June 13, 1951.