


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Stafford County. Sec. 11 Twp. 24S Rge. (E) 14 (W)  
Location as "NE/CNW/SW" or footage from lines C-SW-SW-NW  
Lease Owner Sunray Oil Corporation  
Lease Name Davis Well No. 1  
Office Address Box 195, GreatBend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed October 23 19 51  
Application for plugging filed January 28 19 54  
Application for plugging approved January 29 19 54  
Plugging commenced January 29 19 54  
Plugging completed January 31 19 54  
Reason for abandonment of well or producing formation Formation Depleted

If a producing well is abandoned, date of last production January 12 19 54  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives, Pratt, Kansas  
Producing formation Viola Depth to top 4022 Bottom 4035 Total Depth of Well 4035 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Lansing-KC	Oil	3645	3817	8 5/8	443	none
Viola	Oil	4022	4035	5 1/2	4026	2443

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole 4035' to 4015' with sand and 5 sax cement placed on top of sand. Pulled 64 joints, 2443' of 5 1/2" casing. Mudded hole from 4015 to 445' and ran 100 sax cement. Well plugged and abandoned under supervision of Commission Representative.

Well Log Attached.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Company  
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Barton  
Robert K. Crouch (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Robert K. Crouch  
Box 195, GreatBend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of February, 19 54

My commission expires December 24, 1956

Notary Public.

PLUGGING  
FILE SEC 11 T 24 R 14W  
BOOK PAGE 10 LINE 37

REC'D  
STATE CORP  
2-16-54  
FEB 16 1954

CONSERVATION  
Wichita

DAVIS WELL No. 1

SW SW NW  
SEC. 11-24S-14W  
STAFFORD COUNTY, KANSAS

CONTRACTOR: THE R. W. RINE DRILLING COMPANY  
STARTED: OCTOBER 3, 1951

FINISHED: OCTOBER 18, 1951

LOG

SAND AND CLAY	0 - 120	
SAND AND CLAY	120 - 200	
RED ROCK AND SHELLS	200 - 450	8-5/8" Csg. @ 443' w/350 Sx.
RED CLAY - SHELLS AND SAND	450 - 1090	SYFO @ 500' - SYFO @ 1000' - OK
SAND, SHALE AND SHELLS	1090 - 1525	
SALT AND SHELLS	1525 - 1725	SYFO @ 1500' - OK
SHALE AND SHELLS	1725 - 1825	
LIME	1825 - 1900	
LIME	1900 - 2045	SYFO @ 2000' - OK
LIME AND SHALE	2045 - 2150	
LIME	2150 - 2280	
LIME AND SHALE	2280 - 2385	
LIME AND SHALE	2385 - 2505	SYFO @ 2500' - 1°
SAND AND SHALE	2505 - 2665	
SANDY SHALE	2665 - 2755	
SHALE	2755 - 3010	SYFO @ 3000' - 1°
SHALE AND LIME	3010 - 3270	
LIME	3270 - 3403	
LIME	3403 - 3530	
LIME AND SHALE	3530 - 3635	
LIME	3635 - 3730	
LIME AND SAND, SHALE	3730 - 3777	
LIME	3777 - 3975	
LIME AND CHERT	3975 - 4026	T.D. 5 1/2" Csg. @ 4026' w/150 Sx.

STATE OF KANSAS )  
                          ) ss.  
COUNTY OF SEDGWICK )

I, R. M. GREEN, DO HEREBY CERTIFY THAT THE ABOVE IS A TRUE AND ACCURATE LOG OF THE DAVIS WELL No. 1, LOCATED SW SW NW, SEC. 11-24S-14W, STAFFORD COUNTY, KANSAS.

*R. M. Green*  
ASSISTANT SECRETARY

SUBSCRIBED TO AND SWORN BEFORE ME THIS 27TH DAY OF OCTOBER, 1951.

*Leona Peterson*  
NOTARY PUBLIC

MY COMMISSION EXPIRES APRIL 20, 1955

**PLUGGING**  
FILE SEC. 11 T. 24 R. 14W  
BOOK PAGE 10 LINE 37

FEB 16 1954  
CONSERVATION