

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Stafford SEC. NE 4 TWP. 24 RGE. 19 W
Location as in quarters or footage from lines:

Locate Well
correctly on above
Section Platt.

Lease Owner Woolsey Petroleum Corporation
Lease Name Koelsch Well No. 1
Office Address Suite 400 300 West Douglas Wichita, Ks. 67202
Character of Well (Completed as Oil, Gas or Dry Hole): Oil
Date Well Completed Dec. 8, 1984
Application for plugging filed Oct. 16, 1985
Plugging commenced October 21, 1985
Plugging completed October 25, 1985
Reason for abandonment of well or producing formation Not economical to produce

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well /
Producing formation Lansing Depth to top / bottom T.D. 4250'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				3/4 rods		158
				2 3/8"		126 jts.
				8 5/8"		none
				4 1/2"		52 jts. + 1 cutoff jt.


Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

October 21, 1985 Pulled rods and tubing, dumped 50 sx. sand.
October 22, 1985 Dumped 4 sx. cement, shot off casing at 2134', pulled 52 jts. + 1 cutoff.
Dumped 3 sx. hulls, 15 gel, 70 sx. cement, 10 gel, 1 hulls, 8 5/8 plug, 100 sx. cement.
60-40- poz with 6% gel. On October 25, 1985 dumped 7 sx. cement, filled surface.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pratt Well Service, Inc.

STATE OF Kansas COUNTY OF Pratt, ss.
Judy Berry (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.



(Signature) Judy Berry
Box 847 Pratt, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of Nov., 1985

My Commission expires: Feb. 6, 1989

Dorothy M. Furgason
CORPORATION COMMISSION Notary Public.

NOV 7 1985
11-7-85
CONSERVATION