

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-185-22,415-0000

LEASE NAME Bookstore

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER 2-11

4620 Ft. from S Section Line

4620 Ft. from E Section Line

LEASE OPERATOR Petro Locators, Inc.

SEC. 11 TWP. 24 RGE. 14 (X) or (W)

ADDRESS P.O.Box 77 Pratt, KS 67124

COUNTY Stafford

PHONE#(316) 672-3040 OPERATORS LICENSE NO. 9740

Date Well Completed 2-11-87

Character of Well D&A

Plugging Commenced 2-11-87

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 2-12-87

Did you notify the KCC District Office prior to plugging this well? yes

Which KCC Office did you notify? Dodge City

Is ACO-1 filed? operator to be filed by operator If not, is well log attached? yes

Producing Formation _____ Depth to Top _____ Bottom T.D. 4230

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out

STATE CORPORATION COMMISSION
 2-17-87
 FEB 17 1987
 CONSERVATION DIVISION
 WICHITA, KANSAS

Describe in detail the manner in which the well was plugged, indicating where the plug was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Bottom Plug: @ 870' w/50 sacks cement thru drill pipe
 Next Plug: @ 433' w/50 " " " "
 Top Plug: @ 40' w/ 10 sacks cement
 15 sacks in Rat Hole

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Duke Drilling Co., Inc. License No. 5929

Address Box 823 Great Bend, KS 67530

STATE OF Kansas COUNTY OF Barton, ss.


Leonard Williamson (Employee of Operator) or ~~XXXXXXXXXX~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Leonard Williamson

(Address) Box 823 Great Bend, KS 67530

SUBSCRIBED AND SWORN TO before me this 16 day of February, 1987

Dorothy M Hague
 Notary Public



DRILLER'S WELL LOG

DATE COMMENCED: February 5, 1987
DATE COMPLETED: February 11, 1987

Petro Locators, Inc.
BOOKSTORE 2-11
C NW NW
Sec. 11, T24S, R14W
Stafford County, Ks.

ELEVATION:- 1958 K.B.

0	-	335'	Surface Soil, Sand, Shale, Red Bed
335	-	862'	Cedar Hill, Red Bed, Shale
862	-	885'	Anhydrite
885	-	3086'	Lime & Shale
3086	-	3488'	Lime
3488	-	3509'	Shale & Lime
3509	-	3530'	Lime
3530	-	3627'	Shale
3627	-	3649'	Lime & Shale
3649	-	3907'	Lime
3907	-	4038'	Shale, Lime, Chert, Sand
4038	-	4069'	Chert & Lime
4069	-	4150'	Chert
4150	-	4207'	Sand
4207	-	4230'	Dolomite
		4230'	RTD

FORMATION DATA

Anhydrite	862'
Howard	3086'
Topeka	3169'
Heebner	3486'
Toronto	3509'
Douglas	3530'
Br. Lime	3627'
Kansas City	3549'
Base K.C.	3907'
Conglomerate	4014'
Mississippi	4038'
Viola	4069'
Simpson	4150'
Arbuckle	4207'
RTD	4230'

Surface Pipe: Set new
8-5/8", 20# pipe @403'
w/215 sacks 60/40 pozmix
2% gal 3% cc.

A F F I D A V I T

STATE CORPORATION COMMISSION


STATE OF KANSAS
COUNTY OF BARTON) ss

FEB 17 1987
CONSERVATION DIVISION
Wichita, Kansas

Leonard Williamson of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Leonard Williamson

Subscribed and sworn to before me this 16 day of February 1987.



Dorothy M. Hague
Notary Public