

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Stafford

County. Sec. 10 Twp. 24S Rge. 14 (E) 14 (W)

Location as "NE/CNW/SW" or footage from lines C- SE 1/4 SE 1/4 NE 1/4

Lease Owner Monsanto Chemical Company

Lease Name Davis Well No. 1

Office Address P. O. Box 580, Pratt, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed August 2, 19 51

Application for plugging filed February 18, 19 58

Application for plugging approved February 19, 19 58

Plugging commenced March 25, 19 58

Plugging completed March 28, 19 58

Reason for abandonment of well or producing formation Production Depleted

If a producing well is abandoned, date of last production February 27, 19 58

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Frank Broadfoot

Producing formation Lansing-Kansas City Depth to top 3642' Bottom 3810' Total Depth of Well 4046' Feet

Show depth and thickness of all water, oil and gas formations. PBTD - 3850'

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				9-5/8"	260'	None
				5-1/2"	4026'	2840'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sand from 3850' to 3755', 5 sacks of cement on top of sand.
Pumped 26 sacks of gel mud in hole and mud started circulating around surface casing. Pumped in 75 sacks of cement and circulated around surface casing. Surface casing was filled with cement.

NOTE: Plugged per Mr. Broadfoot's orders.

RECEIVED
STATE CORPORATION COMMISSION
4-1-58
APR 1 1958
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor West Supply Company
Address Chase, Kansas

STATE OF KANSAS, COUNTY OF PRATT, ss.
Bruce E. Roll (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bruce E. Roll
P. O. Box 580, Pratt, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 31st day of March, 19 58

Walter J. Lanza

Notary Public.

My commission expires September 19, 1959

PLUGGING
FILE SEC 10 T 24 R 14C
BOOK PAGE 84 LINE 5

WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

COPY

Company - LION OIL CO.
Farm - Davis

No. 1

SEC. 10 T. 24 R. 14W
SE SE NE

Total Depth. 4046

Comm. 7-9-51

Shot or Treated.

Contractor. Garvey Oil

Issued. 9-22-51

Comp. 7-22-51

County. Stafford
KANSAS



Elevation. 1955

Production. pmp. pot. 140 BOPD

CASING:

9 5/8" 260'
5 1/2" 4031'

Figures Indicate Bottom of Formations.

surface clay, shale	40
shale	50
sand	70
shale, shells	125
shale, lime	260
red bed, shale	875
shale, shells	1260
salt, shale	1440
shale, shells	1875
shale, lime	2010
lime	2075
lime, shale	2465
shale	2600
shale, shells	2915
shale	3002
shale, shells	3300
shale, lime	3753
lime	3787
shale, lime	3823
lime	4015
conglomerate	4034
chert, lime	4046 RTD
Total depth	

Tops:	
Lansing	3642
Conglomerate	4015
Viola	4030

Scout tops:	
Hebner	3489
Brown Lime	3625

Hydrafrac 4031-46

PLUGGING
FILE SEC. 10 T. 24 R. 14W
BOOK PAGE 04 LINE 5

SE
Kansas