


STATE OF KANSAS
STATE CORPORATION COMMISSION
Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

T 24S NORTH 14W



Locate well correctly on above Section Plat

Stafford County. Sec. 10 Twp. 24S Rge. 14W(E) (W)
Location as "NE/CNW/SW" or footage from lines C NL NE SE
Lease Owner Gt. Bend Pipe & Supply Company
Lease Name Koelsch "A" Well No. 2
Office Address West 10th; Gt. Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 9--4--1950
Application for plugging filed 3--31 1956
Application for plugging approved 4--2 1956
Plugging commenced April 20 1956
Plugging completed April 26 1956
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Brundege
Producing formation Viola Depth to top 4049 Bottom _____ Total Depth of Well 4064 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	224'	None
				5-1/2"	4041'	3086'
				Hole plugged back to 3685'. Pipe perforated 3670' to 3675'.		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled the hole with sand from 3685' to 3660' and ran 5 sacks of cement. Pumped 1 sacks of hulls, 15 sacks of mud and 85 sacks of cement into surface pipe. Removed head and checked top of fluid at 8' and top of cement in surface pipe at 68'. Bailed fluid to 68', mudded the hole to 25' and ran 8 sacks of cement on top. Plugging completed.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Co., Inc.
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Barton, ss. Nathan Meltzer (Employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Nathan Meltzer
Box 414; Gt. Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 4th day of May, 19 56

My commission expires 3-30-57

Ann Meltzer
Notary Public.
MAY 8 1956

PLUGGING
PLUG SEC 10 T 24S R 14W
BOOK PAGE 50 LINE 23

CONSERVATION DIVISION
Wichita, Kansas

KANSAS WELL LOG BUREAU --- KANSAS GEOLOGICAL SOCIETY

508 EAST MURDOCK - WICHITA, KANSAS

COMPANY JOHN LINDAS OIL, INC., ET AL


SEC. 10 T. 21 S. 11W

FARM Koelsch "A" No. 2

LOC. CN/2 NE SE

TOTAL DEPTH 4065
 COMM. 8-16-50 COMP. 9-4-50
 SHOT OR TREATED
 CONTRACTOR John Lindas Oil, Inc.
 ISSUED 11-18-50

COUNTY Stafford



CASING
 8 5/8" 224' cem w/ 150 sx
 5 1/2" ~~224'~~ cem w/ 150 sx

ELEVATION 1953

PRODUCTION 157 bbls / trace wtr

4041

FIGURES INDICATE BOTTOM OF FORMATIONS

soil clay, sand	50
shale	110
shale, shells	265
red bed, sand	710
red bed	870
anhydrite	895
red bed	1125
shale, shells	1248
salt, shale	1430
shale, shells	1790
lime, shale	2005
lime sandy	2080
lime	2265
shale, lime, shells	2290
shale, lime	2410
lime, shale	2520
lime	2645
lime, shale	2720
lime broken	2885
lime, shale	3045
lime	3130
lime, shale	3630
lime	4045
lime Viola	4059
lime	4065
Total Depth	

Went to top of well

Scout Tops:

Heebner	3487
Brown Lime	3620
Lansing	3643
Conglomerate	4023
Viola	4049

RECEIVED
 STATE COMMISSION
 APR 2 - 1958
 CONSERVATION DIVISION
 Wichita, Kansas

PLUGGING
 FILE SEC 10 T 24 R 14W
 BOOK PAGE 50 LINE 23