


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Stafford County, Sec. 10 Twp. 24 Rge. (E) 14 (W)
Location as "NE/CNW/SE" or footage from lines SE - NE - SE
Lease Owner Great Bend Pipe & Supply
Lease Name Koelsch "A" Well No. 1
Office Address Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed March 5, 1950 19
Application for plugging filed March 31, 1956 19
Application for plugging approved April 2, 1956 19
Plugging commenced 4 - 10 19 56
Plugging completed 4 - 17 19 56
Reason for abandonment of well or producing formation _____

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well R. M. Brundage
Producing formation Viola Depth to top _____ Bottom _____ Total Depth of Well 4243 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|------|-------|--------|------------|
| | | 0 | 222 | 8 5/8 | | None |
| | | 0 | 4240 | 5 1/2 | | 3269.83' |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with sand from 4243 to 4115 - dumped 5 sks cement with bailer - squeezed well with 15 sks hulls - 15sks jell mud and 90 sks cement by Sun Oilwell Cementing Co.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor R & D Casing Pulling Co. License # 236
Address Box 569 Ellinwood, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Nathan Meltzer (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Nathan Meltzer
Box 414; Gt. Bend, Ks (Address)

SUBSCRIBED AND SWORN TO before me this 27th day of April, 19 56

My commission expires 3-30-57

Nathan Meltzer
Notary Public.

REC
STATE CORP
4-30-56
APR

PLUGGING
FILE SEC 10 7 24 14W
BOOK PAGE 50 LINE 22

CONSERV


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 E. Murdock, Wichita, Kansas

Company - JOHN LINDAS OIL, INC. ETAL
Farm - Koelsch "A" No. 1

SEC. 10 T. 24 R. 14W
SE NE SE

Total Depth. 4243
Comm. 2-16-50 Comp. 3-5-50
Shot or Treated. 1000 acid
Contractor. Lindas Oil, Inc.
Issued. 4-22-50

County. Stafford
KANSAS



Elevation. _____

Production. Pot. 252 bbls / no water

CASING:

8 5/8" 222' cem w/150 sx.
5 1/2" 4240' 150 5+
900
33 46

Figures Indicate Bottom of Formation

| | |
|---------------------|------|
| soil, clay | 15 |
| sand | 165 |
| shale | 260 |
| red bed | 355 |
| sand | 415 |
| red bed, shells | 660 |
| sand | 710 |
| red bed, shells | 855 |
| anhydrite | 882 |
| red bed, shale | 1200 |
| shale | 1245 |
| salt, shale | 1515 |
| shale, shells | 1730 |
| lime, shale | 2110 |
| lime, shale strks | 2220 |
| lime | 2285 |
| lime brkn, shale | 2430 |
| lime, shale | 2700 |
| lime brkn, shale | 3220 |
| lime | 3575 |
| lime brkn | 3608 |
| lime | 3895 |
| lime, shale | 3925 |
| lime | 3968 |
| shale | 4005 |
| lime, shale, chert | 4025 |
| lime cherty, shale | 4055 |
| lime | 4080 |
| lime, chert shale | 4128 |
| lime, chert | 4152 |
| lime | 4200 |
| shale, dolo, cherty | 4219 |
| lime, chert | 4243 |
| Total depth | |

| | |
|--------------|------|
| Tops: Scout | |
| Topeka | 3320 |
| Kansas City | 3634 |
| Conglomerate | 3988 |
| Kinderhook | 4013 |
| Viola | 4028 |
| Simpson | 4158 |
| Arbuckle | 4213 |

*Red
Homer
R+S Pure Bulling*

PLUGGING
FILE SEC 10 T 24 R 14W
BOOK PAGE 50 LINE 22

RECEIVED
STATE CORPORATION COMMISSION
APR 22 1955
CONSERVATION DIVISION
Wichita, Kansas