

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
File or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Stafford County. Sec. 10 Twp. 24S Rge. 14 (SE) (W)

Location as "NE/CNW%SW%" or footage from lines NW NW NE

Lease Owner Welch & Olsson Drilling Co., Inc.

Lease Name Davis Well No. 1

Office Address 1017 Union National Bank Bldg., Wichita, Kansas.

Character of Well (completed as Oil, Gas or Dry Hole) D & A

Date well completed 8-17 19 53

Application for plugging filed 8-17 19 53

Application for plugging approved 8-17 19 53

Plugging commenced 8-17 19 53

Plugging completed 8-17 19 53

Reason for abandonment of well or producing formation D & A

If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives, Box 148, Pratt, Kansas

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	200'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mudded to 245' and set wooden plug. Cemented and displaced
25 sacks cement through drill pipe onto plug. Mudded to
40' and set second plug, filled hole to bottom of well
cellar with 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor _____
Address _____

STATE OF Kansas, COUNTY OF Sedgwick, ss.
R. E. Welch (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. E. Welch

1017 Union National Bank Bldg., Wichita, Kansas.
(Address)

SUBSCRIBED AND SWORN to before me this 19th day of August, 19 53

Marcella J. Davis
Notary Public.

My commission expires Feb. 27, 1956.

Rec'd
10-3-53
247366-5 3-53-20M

PLUGGING
FILED SER 10 T 24 S 14 W
BOOK PAGE 123 LINE 3

WELL LOG

WELCH & OLSSON DRILLING CO. INC.,
CONTRACTOR: Welch & Olsson Drilling Co. Inc.,
Davis No. 1;
NW NW NE Sec. 10, Twp. 24S, Range 14 West,
Stafford County, Kansas.

Elevation: 1965' R. B.
Commenced Drlg.: 7-31-53
Completed Drlg: 8-17-53
Production: D & A

Casing Record:

Set 200' of 8-5/8" with 150 sacks cement.

(Figures indicate bottom of formations)

<u>FORMATIONS:</u>	<u>DEPTHS</u>	<u>FORMATION TOPS</u>
Surface Soil	80'	Heebner 3475' - 1510'
Clay & Shale	130'	Brown Lime 3613' - 1651'
Pyrite	132'	Lansing 3632' - 1667'
Shale & Shells	200'	Cong. 3974' - 2009'
Red Bed	880'	Viola 4037' - 2072'
Anhydrite	900'	Simpson 4150' - 2185'
Shale & Shells	1775'	Arbuckle 4211' - 2246'
Lime & Shale	2610'	
Shale & Shells	2720'	
Shale & Lime	2815'	
Shale & Shells	3210'	
Lime & Shale	3365'	
Lime	3510'	
Shale	3613'	
Brown Lime	3617'	
Shale	3632'	
Lime	3949'	
Conglomerate	4004'	
Shale	4040'	
Lime	4148'	
Simpson Sand	4208'	
Lime	4218'	
T. D.	4233'	

STATE OF KANSAS,

COUNTY OF SEDGWICK, SS:

I hereby certify that the above is a true and correct copy of Drillers Log of Well drilled in the NW NW NE of Sec. 10, Twp. 24S, Range 14 West, Stafford County, Kansas.

WELCH & OLSSON DRILLING COMPANY, INC.,

By: R. E. Welch
R. E. Welch

Subscribed and sworn to before me this 19th day of August, 1953.

My Commission Expires: Feb. 27, 1956.

Marcella H. Davis
Notary Public

PLUGGING
FILED SEP 10 1953
BACK PAGE 123 LINE 3